CANADA

SITE SUMMARY

Chelan County Leavenworth, Washington

S2 T26N R16E S3 T26N R16E S10 T26N R16E S11 T26N R16E

N47°46'15", W120°49'01"

Lower White Pine

Oxbow Reconnection Project Chelan County, Washington

BRIDGE AT BNSF \ MP 1690.5 —

US HIGHWAY 2, MP 81.95

TEMPORARY CONSTRUCTION ACCESS ROAD STARTS NEAR HIGH MOUNTAIN MEADOWS ROAD




RECLAMATION

COVER SHEET

2013-05-0

SHEET G-1




LOCATION MAP

NOT TO SCALE

SHEET INDEX

COVER SHEET	G-1	
PROJECT OVERVIEW	G-2	
SUMMARY OF QUANTITIES, GENERAL NOTES &	SURVEY CONTROL G-3	
ACCESS PLAN	C-1 THRU $C-3$	
ACCESS ROAD DETAILS & NOTES	C-4	
GEOFOAM LIGHTWEIGHT FILL PLAN & DETAILS	C-5	
ACCESS ROAD PROFILE	C-6	
ACCESS ROAD CROSS-SECTIONS	C-7 THRU C-10	
FLOW BYPASS & SITE DEWATERING	C-11	
GRADING PLAN	C-12	
CHANNEL GRADING PROFILE	C-13	
CHANNEL GRADING DETAILS	C-14	
PLANTING PLAN PLAN	L-1	
PLANT SCHEDULE & DETAILS	1-2 THRII 1-4	




OREGON

CHELAN COUNTY, WASHINGTON

NOT TO SCALE

CAD SYSTEM
AutoCAD Rel. 18
CAD FILENAME
LWP_Cover dura

VICINITY MAP



- 1. ANY ITEM NOT SPECIFICALLY DISCUSSED IN THE GENERAL CONTRACT FOR THIS PROJECT OR IN NOTES ON SHEETS IN THE PLANS SHALL BE AS DESCRIBED IN THE <u>STANDARD SPECIFICATIONS FOR ROADS, BRIDGES, AND MUNICIPAL CONSTRUCTION, 2012</u> PUBLISHED BY THE STATE OF WASHINGTON DEPARTMENT OF TRANSPORTATION. THE CONTRACTOR IS RESPONSIBLE TO BE FAMILIAR WITH THE STANDARD SPECIFICATIONS AND TO HAVE ACCESS TO THE STANDARD SPECIFICATIONS AT THE PROJECT SITE TO ENSURE THAT CONSTRUCTION OF THE PROJECT IS IN CONFORMANCE WITH THE STANDARD SPECIFICATIONS.
- 2. THE NOTES ON THIS PLAN SET SUPERSEDE ANY DUPLICATE ITEMS IN THE STANDARD SPECIFICATIONS.
- 3. HORIZONTAL DATUM: STATE PLANE COORDINATE SYSTEM, WASHINGTON NORTH ZONE, NAD83/91, US SURVEY FEET.

 VERTICAL DATUM: NAVD88. FFFT.
- 4. TOPOGRAPHIC MAPPING OF THE PROJECT AREA PERFORMED BY WH-PACIFIC IN 2010, SUPPLEMENTAL TOPOGRAPHIC MAPPING OUTSIDE THE AREA OF CONSTRUCTION IS BASED ON 2010 GPS AND 2006 LIDAR IMAGING, CHELAN COUNTY, WASHINGTON.
- 5. ELEVATIONS AND DISTANCES SHOWN ARE IN FEET AND DECIMALS WITH CONTOUR INTERVALS AT ONE FOOT INCREMENTS.
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR GENERAL SAFETY DURING CONSTRUCTION, AND ALL WORK SHALL CONFORM TO PERTINENT SAFETY REGULATIONS AND CODES. THE CONTRACTOR SHALL BE SOLELY AND COMPLETELY RESPONSIBLE FOR COMPLIANCE WITH ALL APPLICABLE PROVISIONS OF OSHA AND NRS CHAPTER 618, IN THE CONSTRUCTION PRACTICES FOR ALL EMPLOYEES DIRECTLY ENGAGED IN THE CONSTRUCTION OF THIS PROJECT.
- 7. ALL EMPLOYEES MUST COMPLY WITH BNSF SAFETY REQUIREMENTS. THIS INCLUDES BUT IS NOT LIMITED TO, PASSING A SAFETY COURSE, OBTAINING DOCUMENTATION OF SUCCESSFULLY PASSING THE COURSE, AND ADHERING TO REQUIREMENTS IDENTIFIED IN THE COURSE. THE REQUIRED BNSF SAFETY COURSE MAY BE ACCESSED AT THE FOLLOWING WEBSITE: WWW.RAILROADCOURSES.COM.
- 8. A BNSF FLAGGER SHALL BE PRESENT ANY TIME THE CONTRACTOR IS WORKING WITHIN 25 FEET OF THE TRACKS. THE CONTRACTOR SHALL COMMUNICATE WITH THE CONTRACTING OFFICER TO ARRANGE FOR A FLAGGER TO BE PRESENT DURING THESE TIMES
- 9. EXISTING UNDERGROUND UTILITY LOCATIONS HAVE NOT BEEN IDENTIFIED AND ARE NOT SHOWN ON THESE PLANS. THE CONTRACTOR IS RESPONSIBLE TO LOCATE UTILITIES PRIOR TO CONSTRUCTION AND PROTECT UTILITIES DURING CONSTRUCTION AS DESCRIBED IN SECTION 1-07.17 OF THE STANDARD SPECIFICATIONS. THE TELEPHONE NUMBER FOR THE ONE CALL CENTER FOR UTILITY LOCATES IS 1-800-424-5555. THE CONTRACTOR SHALL ALSO CONTACT BNSF TO ENSURE NO SIGNAL OR TELECOM CABLES ARE LOCATED IN THE AREA OF EXCAVATION; THE BNSF SIGNAL AND TELECOM LOCATE REQUEST NUMBER IS 1-800-533-2891.
- 10. PRIOR TO COMMENCEMENT OF WORK, CONTRACTOR SHALL PROVIDE THE CONTRACTING AGENCY WITH A DETAILED CONSTRUCTION SCHEDULE AND WORK PLAN FOR APPROVAL. THE CONTRACTOR SHALL NOT BEGIN ANY CONSTRUCTION WORK UNTIL THE PROJECT SCHEDULE AND WORK PLAN IS APPROVED BY THE CONTRACTING OFFICER.
- 11. ALL CONSTRUCTION SHALL BE CLOSELY COORDINATED WITH THE CONTRACTING OFFICER SO THAT THE QUALITY OF WORK CAN BE CHECKED FOR APPROVAL.
- 12. THE CONTRACTOR SHALL CONSTRUCT AN ACCESS ROAD OFF HIGH MOUNTAIN MEADOWS AT A LOCATION STAKED BY THE CONTRACTING OFFICER. THE CONTRACTOR SHALL USE THE ACCESS ROAD TO ACCESS THE SITE FOR ALL CONSTRUCTION RELATED ACTIVITIES AND SHALL NOT USE DARDANELLE'S ROAD FOR SITE ACCESS. IT IS ANTICIPATED THAT AN UNRELATED CONSTRUCTION PROJECT WILL BE TAKING PLACE CONCURRENT WITH THIS PROJECT IN THE SAME VICINITY; DARDANELLE'S ROAD WILL BE SHUT DOWN AT VARIOUS TIMES DUE TO THAT PROJECT AND SHALL NOT BE USED TO ACCESS THE SITE TO ENSURE NO CONFLICT TO SITE ACCESS FOR EITHER PROJECT WILL OCCUR.
- 13. TRAFFIC ON DARDANELLE'S ROAD HAS THE RIGHT-OF-WAY AT ALL TIMES; CONSTRUCTION TRAFFIC ON THE ACCESS ROAD SHALL YIELD TO TRAFFIC ON DARDANELLE'S ROAD.
- 14. BRIDGE INSTALLATION WILL BE PERFORMED BY BNSF FOLLOWING CONSTRUCTION OF THE ACCESS ROAD; THE CONTRACTOR SHALL MAINTAIN CLOSE COORDINATION WITH THE CONTRACTING OFFICER REGARDING THE TIMING OF WORK TO AVOID CONFLICTS WITH BRIDGE INSTALLATION OR RELATED ACTIVITIES.

- 15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE SITE IN A NEAT AND ORDERLY MANNER THROUGHOUT THE CONSTRUCTION PROCESS. ALL MATERIALS SHALL BE STORED WITHIN APPROVED CONSTRUCTION STAGING AREAS.
- 16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING, AT THE CONTRACTOR'S EXPENSE, ALL CONSTRUCTION PERMITS
 AS REQUIRED BY THE LOCAL AGENCIES. THE CONTRACTOR SHALL PROVIDE ALL MATERIALS, LABOR AND EQUIPMENT REQUIRED
 TO COMPLY WITH ALL APPLICABLE PERMIT CONDITIONS AND REQUIREMENTS. THE CONTRACTING AGENCY HAS SECURED
 ENVIRONMENTAL PERMITS FOR THE PROJECT; THE CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS LISTED IN THE
 PERMITS.
- 17. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION STAKING AND LAYOUT, UNLESS OTHERWISE SPECIFIED IN THE DRAWINGS. HORIZONTAL AND VERTICAL ALIGNMENT DATA FOR EXCAVATIONS AND FILLS ARE INCLUDED IN THESE PLANS.
- 18. THE CONTRACTOR SHALL PLACE TEMPORARY COFFERDAMS BETWEEN THE ACTIVELY FLOWING CREEK OR PONDED WATER IN THE OXBOW AREA AND THE EXTENTS OF ANY EXCAVATION TO KEEP WATER AND FISH FROM ENTERING THE ACTIVE CONSTRUCTION AREA. TWO COFFERDAMS WILL BE REQUIRED TO COMPLETE THE WORK SHOWN ON THESE PLANS, ONE ON THE NASON CREEK SIDE OF THE RAILROAD EMBANKMENT AND ONE ON THE OXBOW SIDE. THE COFFERDAM ON THE NASON CREEK SIDE OF THE EMBANKMENT SHALL BE INSTALLED BETWEEN JULY 1, AND AUGUST 10, 2013. THE NASON CREEK COFFERDAM SHALL REMAIN IN PLACE FROM INSTALLATION UNTIL OCTOBER 15, 2013. THE NASON CREEK COFFERDAM SHALL BE REMOVED ON OCTOBER 15, 2013. THE COFFERDAM ON THE OXBOW SIDE OF THE RAILROAD EMBANKMENT SHALL BE INSTALLED AFTER INSTALLATION OF THE NASON CREEK COFFERDAM; THE OXBOW COFFERDAM MAY BE REMOVED PRIOR TO BUT NO LATER THAN OCTOBER 15, 2013.
- 19. THE CONTRACTOR SHALL NOTIFY THE CONTRACTING OFFICER A MINIMUM OF 5 WORKING DAYS IN ADVANCE OF COFFERDAM CONSTRUCTION TO COORDINATE FISH REMOVAL. THE CONTRACTING AGENCY WILL BE RESPONSIBLE FOR ALL FISH REMOVAL AND HANDLING
- 20. DEWATERING WITHIN COFFERDAMS SHALL BE PERFORMED TO THE EXTENT NECESSARY, AS DETERMINED BY THE CONTRACTOR, TO CONSTRUCT THE PROJECT AS SHOWN ON THESE PLANS. DISCHARGE FROM DEWATERING WITHIN THE WORK AREA SHALL BE ROUTED TO A SMALL SETTLING BASIN OR OTHER WDFW—APPROVED DETENTION OR FILTERING SYSTEM, AND TEMPORARILY DETAINED OR FILTERED SO AS TO ALLOW THE REMOVAL OF FINE SEDIMENTS OR OTHER CONTAMINANTS PRIOR TO BEING ALLOWED TO REENTER NASON CREEK OR WETLANDS. ALL PUMPS USED BY THE CONTRACTOR FOR DEWATERING SHALL HAVE SCREENED INTAKES THAT MEET WOFW SPECIFICATIONS AND JUVENILE FISH SCREENING CRITERIA.
- 21. ALL EQUIPMENT CONDUCTING IN—WATER WORK, WORKING WITHIN THE ACTIVELY FLOWING CREEK CHANNEL, WORKING WITHIN THE CHANNELS OR STANDING WATER AREAS OF THE OXBOW, AND WORKING ON THE TOP OF BANK ADJACENT TO THE ACTIVELY FLOWING CREEK CHANNEL, SHALL USE VEGETABLE OIL FOR HYDRAULIC FLUID.
- 22. MATERIAL EXCAVATED DURING CHANNEL EXCAVATION SHALL BE STOCKPILED ON BNSF PROPERTY AT THE LOCATION SHOWN ON SHEETS G-2 AND C-3. THE MATERIAL SHALL BE PLACED ON AND COVERED BY PLASTIC SHEETING WITH A MINIMUM THICKNESS OF 10 MILS, AND SANDBAGS SHALL BE PLACED ON THE PLASTIC SHEETING TO HOLD IT IN PLACE. THE STOCKPILE SHALL REMAIN IN PLACE UNTIL TESTING FOR CONTAMINANTS HAS BEEN COMPLETED BY THE CONTRACTING AGENCY; AFTER TESTING IS COMPLETE, THE CONTRACTOR SHALL HAUL THE STOCKPILED MATERIAL TO A LEGAL DISPOSAL SITE IDENTIFIED BY THE CONTRACTOR. FOR MORE INFORMATION REFER TO SECTION 2-03.3(14)M OF THE SPECIAL PROVISIONS

SUMMARY OF QUANTITIES

ITEM NO.	QUANTITY	UNITS	ITEM
1	LUMP SUM	LS	MOBILIZATION
2	LUMP SUM	LS	SPCC PLAN
3	0.85	AC	CLEARING
4	5,000	DOLLAR	EROSION AND WATER POLLUTION CONTROL
5	1	EA	BEAVER DAM REMOVAL
6	LUMP SUM	LS	INSTALL ACCESS ROAD
7	600	CY	GEOFOAM LIGHTWEIGHT FILL
8	1	EA	ACCESS CONTROL GATE
9	475	LF	FLOATING SILT CURTAIN
10	LUMP SUM	LS	COFFERDAMS
11	LUMP SUM	LS	OXBOW FLOW BYPASS
12	LUMP SUM	LS	DEWATERING
13	1,680	CY	CHANNEL EXCAVATION
14	1,680	CY	HAUL STOCKPILED SOIL
15	<i>375</i>	TON	RIPRAP - CLASS A
16	LUMP SUM	LS	SURVEYING
17	1.24	AC	SEEDING & MULCHING
18	50	EA	PLANTING - LIVE STAKES
19	170	EA	PLANTING - 10 C.I. CONTAINER
20	50	EA	PLANTING - 40 C.I. CONTAINER
21	80	SY	PRE-PLANTED COIR MAT
22	5,000	DOLLAR	MINOR CHANGE

CONTROL TABLE PROJECT LINE COORDINATES

OONTDOL DOLLT	NODTUNO	FACTURE	EL EL MELON	DECORUBION
<u>CONTROL POINT</u>	NORTHING	EASTING	ELEVATION	DESCRIPTION
4	1 <i>647305.75</i>	280161.75	2150.86	REBAR W/ CAP
<i>32</i>	1647111.38	280228.48	2149.66	REBAR W/ CAP
<i>33</i>	1646754.11	280355.68	2150.36	REBAR W/ CAP
50	1647413.65	280171.58	2146.77	REBAR W/ CAP
52	1647126.90	280358.76	2142.02	REBAR W/ CAP
9024	1648396.19	280194.23	2155.46	MON — 2" ALUM. DISK
9025	1648396.84	279890.30	2163.51	MON — 2" ALUM. DISK
9033	1648397.25	279706.07	2157.37	MON — 3" BRASS DISK

CHANNEL LINE COORDINATES

<u>STATION</u> 100+00

104+00

108+00

112+00

116+00 118+00

STATION	NORTHING	<i>EASTING</i>	
0+00	280413.77	1646771.29	
0+50	280366.65	1646754.57	
1+00	280319.53	1646737.86	

280387.82

280253.83

280119 83

279985.84

279851.84

279784.84

1646700.16

1647077.05 1647453.94

1647830.83

1648207.71

1648396.16

RECLAMATION





NEW OF THE WITERIOR
OF RECUMENTON
NECOUNTENT PROGRAM
IMPROVEMENT PROGRAM

IEE SUBBASIN
SOW RECONNECTION PROJECT
WITHES, GENERAL NOTES
IEF CONTROL

COLUMBIA SNAKE RIVER SALMON RECOVER
FORPS HABITAT IMPROVEME
WENATCHEE SU
LOWER WHITE PINE OXBOW RECY
SUMMARY OF QUANTITIES
& SURVEY CON

ON VOR

I. TRUSCOTT


NAME TITLE BOISE, ID


SUMMARY OF QUANTITIES GENERAL NOTES & SURVEY CONTROL


2013-05-


SHEET G-3
SHEET 3 OF 21


CAD SYSTEM
AutoCAD Rel. 18.0s
CAD FILENAME

















RECLAMATION - PROJECT LINE - PROJECT LINE - PROJECT LINE 2160_T 2160_T 2160_T - EX. GROUND EX. GROUND ACCESS ROAD ACCESS ROAD IN PASSING ZONE ACCESS ROAD 2130 DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) <u>SECTION 104+50</u> <u>SECTION 105+00</u> <u>SECTION 105+50</u> INTERNATIONAL PROJECT LINE - PROJECT LINE - PROJECT LINE SAFET SNAKE RIVER SALMON TRECOVERY PROCERM –
FORPS HABITAT IMPROVEMENT PROCESUM

WENATCHEE SUBBASIN


R WHITE PINE OXBOW RECONNECTION P


ACCESS ROAD CROSS—SECTIONS 2160_T 2160_T EX. GROUND - EX. GROUND ACCESS ROAD ACCESS ROAD IN ACCESS ROAD IN PASSING ZONE TURN AROUND ZONE ALWAYS 2130 2130 2130 30 DISTANCE FROM ALIGNMENT &(FEET) DISTANCE FROM ALIGNMENT &(FEET) DISTANCE FROM ALIGNMENT & (FEET) SECTION 106+00 *SECTION 106+50* SECTION 107+00 PROJECT LINE PROJECT LINE PROJECT LINE 2160_{T} 2160 $2160_{\rm T}$ EX. GROUND - EX. GROUND - FX. GROUND (FEE) ACCESS ROAD ACCESS ROAD ACCESS ROAD 2130 2130 30 DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) SECTION 107+50 SECTION 108+00 **SECTION 108+50 NOTES** 1. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION STAKING. 2013-05-0 BOISE, ID 2. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE OCCURRING TO RAILROAD AS A RESULT OF CONSTRUCTION ACTIVITIES. ALL WORK CONDUCTED BY THE CONTRACTOR SHALL ACCESS ROAD CROSS-SECTIONS COMPLY WITH BNSF SAFETY REQUIREMENTS. CAD SYSTEM
AutoCAD Rel. 1
CAD FILENAME
LWP_ACCOCCO AIII SHEET C-8 SHEET 11 OF 21

RECLAMATION - PROJECT LINE - PROJECT LINE - PROJECT LINE $2160_{\rm T}$ 2160_T 2160_T - EX. GROUND - EX. GROUND EX. GROUND 2150 ACCESS ROAD ACCESS ROAD ACCESS ROAD 5/8/2013 EFENA 2140 2130 DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) <u>SECTION 109+00</u> <u>SECTION 109+50</u> <u>SECTION 110+00</u> INTERNATIONAL - PROJECT LINE - PROJECT LINE - PROJECT LINE SAFET *2160*⊤ SNAKE RIVER SALMON TRECOVERY PROGRAM – FCRPS HABITAT IMPROVEMENT PROGRAM WENATCHEE SUBBASIN

WENATCHEE ONBO RECONNECTION PACCESS ROAD CROSS—SECTIONS 2160_T 2160_T EX. GROUND EX. GROUND EX. GROUND ACCESS ROAD ACCESS ROAD ACCESS ROAD ALWAYS 2130 2130 DISTANCE FROM ALIGNMENT &(FEET) DISTANCE FROM ALIGNMENT &(FEET) DISTANCE FROM ALIGNMENT & (FEET) SECTION 111+50 SECTION 110+50 *SECTION 111+00* PROJECT LINE PROJECT LINE - PROJECT LINE 2160_T 2160 2160 EX. GROUND EX. GROUND ACCESS ROAD FX. GROUND (FEET) ACCESS ROAD NOIT 2130 2130 30 DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) SECTION 112+00 SECTION 112+50 **SECTION 113+00 NOTES** 1. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION STAKING. 2013-05-0 BOISE, ID 2. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE OCCURRING TO RAILROAD AS A RESULT OF CONSTRUCTION ACTIVITIES. ALL WORK CONDUCTED BY THE CONTRACTOR SHALL ACCESS ROAD CROSS-SECTIONS COMPLY WITH BNSF SAFETY REQUIREMENTS. CAD SYSTEM
AutoCAD Rel. 1
CAD FILENAME
LWP Access dw SHEET C-9 SHEET 12 OF 21

C-10 | RECLAMATION 2170_T 2170_T $2170_{
m I}$ PROJECT LINE PROJECT LINE 2160 (HE EX. GROUND EX. GROUND EX. GROUND ACCESS ROAD ACCESS ROAD ACCESS ROAD EF. 2150 DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) <u>SECTION 113+50</u> *SECTION 114+00* <u>SECTION 114+50</u> INTERNATIONAL SAFET SNAKE RIVER SALMON RECOVERY PROGRAM – FCRPS HABITAL IMPROVEDRIN PROGRAM WENATION PLACES ROAD CROSS-SECTIONS PROJECT LINE PROJECT LINE $2170_{
m T}$ PROJECT LINE 2160 EX. GROUND EX. GROUND ACCESS ROAD FX. GROUND ACCESS ROAD ACCESS ROAD ALWAYS 2140 2140 DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) SECTION 116+00 *SECTION 115+50* SECTION 115+00 - PROJECT LINE PROJECT LINE 2170_T $2170_{\rm T}$ EX. GROUND ACCESS ROAD EX. GROUND ACCESS ROAD 2140 30 DISTANCE FROM ALIGNMENT & (FEET) DISTANCE FROM ALIGNMENT & (FEET) SECTION 116+50 SECTION 117+00 **NOTES** 1. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION STAKING. 2013-05-0 BOISE, ID 2. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE OCCURRING TO RAILROAD AS A RESULT OF CONSTRUCTION ACTIVITIES. ALL WORK CONDUCTED BY THE CONTRACTOR SHALL ACCESS ROAD CROSS-SECTIONS COMPLY WITH BNSF SAFETY REQUIREMENTS. CAD SYSTEM
AutoCAD Rel. 1
CAD FILENAME
LWP Access.dw SHEET C-10 SHEET 13 OF 21







C-13 | RECLAMATION 5/8/2013 2160-BRIDGE CONSTRUCTED BY OTHERS BRIDGE WILL BE COMPLETED PRIOR TO EXCAVATION BEGINNING EXISTING GROUND PRIOR TO BRIDGE INSTALLATION MATERIAL REMOVED BY OTHERS DURING BRIDGE INSTALLATION REMOVE ACCESS ROAD FILL, CONTRACTOR RESPONSIBLE FOR DISPOSAL OF MATERIAL 2150 - EXISTING GROUND AFTER BRIDGE INSTALLATION EXCAVATE CHANNEL THROUGH RAILROAD — EMBANKMENT, STOCKPILE MATERIAL AT LOCATION SHOWN ON THESE PLANS 2145 SAFET MON RECOVENT PROGRAM

3. HEE SUBBASIN

SXBOW RECONNECTION I

GRADING PROFILE □ ORDINARY HIGH WATER 2140 GRADING BEGINS AT STA 0+11.28 CHANNEL GRADING ENDS -AT STA 0+96.82 CHANNEL LINE Q-FINISHED ELEV = 2134.0' 2135 KE RIVER SALMON RECC FCRPS HABITAT IMPROV WENATCHEE S HITE PINE OXBOW F CHANNEL GRADII ALWAYS 2130-0+75 0+'00 0+25 1+00 CHANNEL LINE PROFILE NOTES 1. BRIDGE WILL BE CONSTRUCTED BY BNSF UNDER SEPARATE CONTRACT. THE EXCAVATION UNDER BRIDGE WILL OCCUR AFTER THE BRIDGE IS COMPLETED. THE CONTRACTOR IS RESPONSIBLE TO REPAIR OR REPLACE ANY BRIDGE AND/OR RAILROAD COMPONENTS DAMAGED BY THE CONTRACTOR'S OPERATIONS. CONTRACTOR MAY BE HELD FINANCIALLY RESPONSIBLE FOR COSTS ASSOCIATED WITH RAIL SHUTDOWN DUE TO DAMAGE CAUSED BY 2. MATERIAL EXCAVATED DURING CHANNEL EXCAVATION SHALL BE STOCKPILED ON BNSF PROPERTY AT THE LOCATION SHOWN ON SHEETS G-2 AND C-3. THE MATERIAL SHALL BE PLACED ON AND COVERED BY PLASTIC SHEETING WITH A MINIMUM THICKNESS OF 10 MILS, AND SANDBAGS SHALL BE PLACED ON THE PLASTIC SHEETING TO HOLD IT IN PLACE. THE STOCKPILE SHALL REMAIN IN PLACE UNTIL TESTING FOR CONTAMINANTS HAS BEEN COMPLETED BY THE CONTRACTING AGENCY; AFTER TESTING IS COMPLETE, THE CONTRACTOR SHALL HAUL THE STOCKPILED MATERIAL TO A LEGAL DISPOSAL SITE IDENTIFIED BY THE CONTRACTOR. FOR MORE INFORMATION REFER TO SECTION 2-03.3(14)M OF THE SPECIAL PROVISIONS. 2013-05-0 BOISE, ID CHANNEL GRADING PROFILE SYSTEM
CAD Rel. 1
FILENAME CHANNEL GRADING PROFILE SHEET C-13 SHEET 16 OF 21





RIPARIAN EDGE	ID	SPECIES NAME	COMMON NAME	TYP. SPACING	QUANTITY	SIZE
1430 SQ FT	CMAT	SEE COIR MAT PLANT LIST (THIS SHEET)	PRE-PLANTED COIR MAT	AT DIRECTION OF C.O.	80 SY	N/A
	CAOB	CAREX OBNUPTA	SLOUGH SEDGE	2'	100	10 C.I. CONT.
	SCMI	SCIRPUS MICROCARPUS	PANTICLED BULRUSH	2'	70	10 C.I. CONT.
WETLAND						
1650 SQ FT	COSE	CORNUS SERICEA	RED-OSIER DOGWOOD	4'	30	40 C.I. CONT.
	SALA	SALIX LUCIDA SSP. LASIANDRA	PACIFIC WILLOW	4'	30	36" LIVE STAKE
	SASI	SALIX SITCHENSIS	SITKA WILLOW	4'	20	36" LIVE STAKE
	SPD0	SPIREA DOUGLASII	DOUGLAS SPIREA	4'	20	40 C.I. CONT.

PLANT SCHEDULE NOTES

- 1. DENSITY AND DISTRIBUTION OF PLANTS SHALL DEPEND ON SITE CONDITIONS AND SHALL BE SET AT THE DIRECTION OF THE CONTRACTING OFFICER.
- 2. PLANT MATERIAL WILL BE PROVIDED AT NO ADDITIONAL COST TO THE CONTRACTOR. THE CONTRACTOR SHALL FURNISH ALL OTHER MATERIALS REQUIRED TO INSTALL PLANTS AS SHOWN ON THESE PLANS, INCLUDING WOOD CHIP MULCH (5 CY) AND PLANT TUBES (50).

PRE-PLANTED COIR MAT SPECIES SELECTION

ID	SPECIES NAME	COMMON NAME	
CA	CAREX AQUATILIS	WATER SEDGE	
CL	CAREX LANGUINOSA	WOOLY SEDGE	
CN	CAREX NEBRASCENSIS	NEBRASKA SEDGE	
CU	CAREX UTRICULATA	BEAKED SEDGE	
JB	JUNCUS BALTICUS	BALTIC RUSH	

PRE-PLANTED COIR MAT NOTES

- 1. PRE-PLANTED COIR MATS WILL BE PROVIDED AT NO ADDITIONAL COST TO THE CONTRACTOR AND WILL CONTAIN AT LEAST 3 SPECIES FROM THE TABLE ABOVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING ALL OTHER MATERIAL REQUIRED TO INSTALL SEDGE MATS AS SHOWN ON THESE PLANS, INCLUDING WOODEN STAKES (128).
- 2. PLANTS SHALL BE MATURE ENOUGH AS TO PROVIDE COVERAGE TO APPROXIMATELY 50 PERCENT OF THE COIR MAT.
- 3. SEE PRE-PLANTED COIR MAT INSTALLATION DETAILS (SHEET L-4) FOR INSTALLATION DETAILS.

SEED MIX	SPECIES NAME	COMMON NAME	PLS/ACRE
0.97 ACRES	ACHNATHERUM HYMENOIDES	INDIAN RICEGRASS	12
	AGROPYRON SPICATUM	BLUEBUNCH WHEATGRASS	12
	ELYMUS TRACHYCAULUS	SLENDER WHEATGRASS	8
	FESTUCA IDAHOENSIS	IDAHO FESCUE	6
	TRITICUM AESTIVUM X SECALE CEREALE	STERILE TRITICALE	60

SANDBERG BLUEGRASS

SEED MIX


SEEDING NOTES

- 1. FOLLOWING CONSTRUCTION, THE PORTION OF THE ACCESS ROAD WEST OF DARDANELLE'S ROAD, THE STAGING AREA, AND THE AREA DISTURBED FROM STOCKPILING EXCAVATED MATERIAL SHALL BE SEEDED ACCORDING TO THE SEED MIX AND APPLICATION RATES SHOWN ON THIS SHEET.
- 2. ALL SEEDING AREAS SHALL BE PREPARED IN ACCORDANCE WITH SECTION 8-01.3 OF THE STANDARD SPECIFICATIONS. SEEDING AREAS NEED NOT BE CULTIVATED, BUT SHALL BE RAKED OR CHAINED TO ENSURE A FRIABLE SURFACE FREE OF SOIL CLUMPS LARGER THAN 2 INCHES IN
- 3. APPLICATION OF SEED SHALL BE FOLLOWED BY THE APPLICATION OF STRAW MULCH APPLIED AT A RATE OF 2 TONS/ACRE (2.48 TONS TOTAL).
- 4. THE SEED MIX SPECIFIED ABOVE WILL BE PROVIDED TO THE CONTRACTOR AT NO ADDITIONAL COST. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING ALL OTHER MATERIALS REQUIRED TO SEED AS SHOWN ON THESE PLANS.

TYPICAL PLANTING CROSS-SECTION NOTES

POA SECUNDA

- 1. THIS TYPICAL CROSS-SECTION IS INTENDED AS A GENERAL GUIDE TO PLANTING NEAR THE BREACH OF THE RAIL PRISM. SEE SHEET L-1 FOR LOCATION AND EXTENT OF ALL PLANTING AREAS.
- 2. PLANT INSTALLATION SHALL OCCUR UNDER THE DIRECTION OF CONTRACTING OFFICER. LOCATION AND EXTENT OF PLANTING AREAS MAY CHANGE BASED ON SITE CONDITIONS.
- 3. THE ANTICIPATED WATER SURFACE ELEVATION SHOWN ON THIS SHEET IS AN ESTIMATE OF LIKELY CONDITIONS AT THE TIME OF PLANTING. CONDITIONS MAY VARY. RIPARIAN EDGE PLANTINGS MAY BE INSTALLED IN WATER UP TO 4 INCHES DEEP.
- 4. PLANTINGS SHALL MAINTAIN A 25 FOOT OFFSET FROM THE PROJECT LINE (CENTER OF TRACKS).



TYPICAL PLANTING CROSS-SECTION

Rel.

RECLAMATION

IRS





OVEMENT PROGRAM

SUBBASIN

RECONNECTION

LE & DETAILS SA MENATCHEE SHAWOV REC.
- MVER SHAWOV RECO.
FCRPS HABITAT IMPROV.
WENATCHEE S.
WHITE PINE OXBOW PH

ALWAYS

BOISE. ID

PLANT SCHEDULE & DETAILS

2013-05-0

SHEET L-2 SHFFT 19 OF 21

INSTALL 15" PLANT TUBE AROUND BASE OF PLANT (SEE ON SLOPES; PLANTS NOTE 5) INSTALLED UPRIGHT AND SOIL LEVELED AT PLANTING HOLE TOP OF ROOTBALL EVEN WITH LOCATION (SEE NOTE 3) -FINISH GRADE (SEE NOTE 3) 3' DIAMETER RING OF WOOD CHIP MULCH 4" DEEP ON 40 C.I. CONTAINER PLANTS (SEE NOTE 6) FINISH GRADE ROOTS SPREAD INTO PLANTING HOLE (SEE NOTE 3) 2x GREATER PLANTING HOLE BACKFILLED SOIL THAN WIDTH OF (SEE NOTE 4) ROOTBALL 40 CUBIC INCH CONTAINER PLANT INSTALLATION

- OUTER 1" OF ROOTBALL. CLEANLY PRUNE BROKEN, DEAD, OR DISEASED ROOTS. ROOTBOUND PLANTS
- 2. EXCAVATE CIRCULAR PLANTING HOLE WITH VERTICAL SIDES. SCARIFY SIDES AND BOTTOM OF PLANTING
- HOLE. PLANTS SHALL BE UPRIGHT, PLUMB, AND TOP OF ROOTBALL SHALL BE EVEN WITH FINISH GRADE. WHEN PLANTING ON SLOPES, CREATE LEVEL PLANTING SURFACE TO ENSURE COVER OF ROOTS
- BASE OF THE PLANT PER MANUFACTURER'S INSTRUCTIONS.
- 7. WITHIN 4 HOURS OF PLANT INSTALLATION, THOROUGHLY WATER IN EACH INSTALLED PLANT.

- 1. LIVE STAKES SHALL BE AS DESCRIBED IN SECTION 9-14.6 OF THE STANDARD SPECIFICATIONS. LIVE STAKES SHALL BE COLLECTED FROM PLANTS WITHIN THE NASON CREEK
- 2. LIVE STAKES SHALL BE BETWEEN 1/2" AND 1 1/2" DIAMETER AND OF SPECIES AND LENGTH INDICATED ON THE PLANT
- 3. LIVE STAKES WHICH ARE NOT PLANTED WITHIN 8 HOURS OF CUTTING SHALL BE SOAKED IN WATER FOR 24-72 HOURS PRIOR TO INSTALLATION. STAKES WHICH HAVE DEVELOPED ROOTS SHALL NOT BE USED.
- INSTALLATION.

LIVE STAKE INSTALLATION

NOT TO SCALE

LIVE STAKES SHALL

BETWEEN 1/2" AND 1 1/2"

HAVE A DIAMETER

- MINIMUM 3 BUD SCARS

- FINISH GRADE

ABOVE GROUND (SEE NOTE 4)

UNDISTURBED NATIVE SOIL

PILOT HOLE BACKFILLED WITH NATIVE SOIL (SEE NOTE 5)

OVEMENT PROGRAM

SUBBASIN

RECONNECTION

LE & DETAILS SAFI WE RIVER BALMON BECC FCRPS HABITAT IMPROV WENATCHEE S HHITE PINE OXBOW R ALWAYS 2013-05-0 BOISE. ID

> PLANT SCHEDULE & DETAILS


SHEET L-3 SHFFT 20 OF 21

RECLAMATION

5/8/2013

CONTAINER PLANT INSTALLATION NOTES:

PRIOR TO INSTALLATION OF CONTAINER PLANT, CLEANLY PRUNE ANY BROKEN BRANCHES AND SCARIFY



4. BACKFILL PLANTING HOLE WITH SOIL EXCAVATED FROM PLANTING HOLE AND TAMP SOIL AROUND ROOTS.
ANY TRASH OR DEBRIS FOUND IN EXCAVATED SOIL SHALL NOT BE USED TO BACKFILL THE PLANTING HOLE. BACKFILL SOIL SHALL MAKE GOOD CONTACT WITH THE ROOTBALL, LEAVING NO VOIDS.

- 5. EACH CONTAINER PLANT SHALL HAVE A 15" TRANSLUCENT PLASTIC GROW TUBE INSTALLED AROUND THE
- 6. ALL 40 CUBIC INCH CONTAINER STOCK PLANTS SHALL BE MULCHED WITH A 3 FOOT DIAMETER 4 INCH DEEP RING OF WOOD CHIP MULCH. MULCH SHALL BE KEPT OFF OF THE BASE OF PLANTS.

LIVE STAKE INSTALLATION NOTES:

- SCHEDULE (THIS SHEET).
- 4. IF NECESSARY, CREATE PILOT HOLE IN SOIL PRIOR TO
- 5. INSTALL STAKES PERPENDICULAR TO FINISH GRADE WITH BUDS ORIENTED UPWARD. IF STAKES MUST BE POUNDED IN, USE DEAD-BLOW HAMMER. INSTALL STAKES SUCH THAT 2 FEET MINIMUM OF THE LENGTH OF THE ENTIRE STAKE IS IN SOIL AND SUCH THAT A MINIMUM OF 3 BUD SCARS REMAIN ABOVE FINISH GRADE. AVOID DAMAGING THE BUDS PRIOR TO AND DURING STAKE INSTALLATION.
- 6. AFTER INSTALLATION, BACKFILL AND WASH SOIL INTO PILOT HOLE SUCH THAT SOIL MAKES GOOD CONTACT WITH THE STAKE, LEAVING NO VOIDS.
- 7. WITHIN 4 HOURS OF INSTALLATION, THOROUGHLY WATER IN EACH INSTALLED STAKE.

Rel.

10 CUBIC INCH PLANT INSTALLATION NOTES: STEP 5. STEP 3. STEP 2. STEP 4. STEP 1. INSERT TOOL 1. USE A SHOVEL, SPADE OR DIBBLE TO CREATE A PLANTING HOLE LARGE NEXT TO PLANTING ENOUGH TO ACCOMODATE THE ROOT MASS AND SOIL OF THE PLUG WITHOUT BENDING ROOTS AND SUCH THAT THE TOP OF THE ROOT MASS BACKFILL WITH NATIVE HOLE AND PUSH SOIL; LIGHTLY TAMP TO REMOVE AIR POCKETS AWAY FROM PLUG CAN BE PLACED LEVEL WITH THE EXISTING GROUND. USE SHOVEL, TO PRESS SOIL SPADE, OR AGAINST BASE OF 2. PLACE THE PLUG INTO THE PLANTING HOLE WITH THE TOP OF THE DIBBLE TO CREATE ROOT MASS LEVEL WITH EXISTING GROUND. INSERT TOOL NEXT TO THE PLANTING HOLE MOVE TOOL AWAY FROM PLUG AND PULL TOOL BACK PLANTING HOLE TO THE DEPTH OF THE PLANTING HOLE. PUSH TOOL TOWARD PLANT TO SECURE SOIL AWAY FROM PLANTING HOLE TO MOVE SOIL AGAINST THE BASE OF THE BACK TO PRESS 5/8/2013 PLUG'S ROOT MASS. INSERT PLUG WITH TOP AGAINST TOP OF SOIL AGAINST ROOT MASS 3. INSERT TOOL TO HALF OF PLUG'S ROOT DEPTH. PULL TOOL TOWARD THE PLANTING HOLE TO SECURE SOIL AGAINST THE TOP OF THE ROOTS. OF ROOT MASS LEVEL ROOTS WITH EXISTING GROUND 4. INSERT TOOL TO FULL DEPTH OF PLUG ROOTS. MOVE TOOL AWAY FROM PLANTING HOLE AND BACK TOWARD PLANTING HOLE TO PRESS SOIL 5. BACKFILL WORK HOLE WITH NATIVE SOIL. REPEAT ON OTHER SIDES OF PLUG AS NEEDED TO ENSURE NO VOIDS AROUND THE ROOT MASS. **INTERNATIONAL** 6. SECURE PLUG WITH A BAMBOO SKEWER, OR BIODEGRADABLE EQUIVALENT, THROUGH THE TOP OF THE ROOT MASS AND INTO THE NATIVE SOIL. INSERT TOOL TO FULL DEPTH OF INSERT TOOL PI UG TO HALF OF ROOTS PLUG ROOT SECURE ALL PLUGS WITH DFPTH OVEMENT PROGRAM

SUBBASIN

RECONNECTION

LE & DETAILS BAMBOO SKEWER OR **EQUIVALENT** SA $\widehat{\ \ }$ 10 CUBIC INCH CONTAINER PLANT INSTALLATION KE RIVER SALMON RECC FCRPS HABITAT IMPROVI WENATCHEE WHITE PINE OXBOW F L-4 NOT TO SCALE ALWAYS PRE-PLANTED COIR MATS INSTALLATION NOTES: 5 FEET MAX. 16 INCH WOODEN STAKE BETWEEN STAKES PRE-PLANTED COIR MAT DELIVERY SHALL BE SCHEDULED TO COINCIDE WITH IMMEDIATE JOB SITE INSTALLATION. IF MATS CANNOT BE IMMEDIATELY INSTALLED, THEY SHALL BE STORED IN A SHADY LOCATION FOR NO MORE THAN THREE DAYS AND SHALL BE KEPT THOROUGHLY SATURATED AND COVERED DURING THAT TIME. 2. PLANTING AREAS SHALL BE CLEARED OF LARGE ROCKS, TREE BRANCHES, OR OTHER OBJECTS THAT WOULD PREVENT THE MAT FROM MAKING DIRECT CONTACT WITH THE SOIL. VERY ROUGH GROUND SHALL BE SMOOTHED PRIOR TO MAT 3. MATS SHALL BE MOVED TO THE INSTALLATION SITE, UNROLLED AND STAKED DOWN. ENSURE THAT THE PLANT ROOTS AND THE BOTTOM OF THE MAT ARE IN DIRECT CONTACT WITH THE SOIL PRIOR TO STAKING. LEAVE NO VOIDS. 4. ALL EDGES SHALL BE STAKED WITH 16" WOODEN STAKES SPACED AT A MAXIMUM OF EVERY 5 FEET ALONG THE EDGE OF THE MAT. STAKES SHALL BE INSTALLED 1 TO 3 INCHES FROM THE EDGE OF THE MAT. INSTALL STAKES 1 TO 3 5. STAKES SHALL BE INSTALLED AT AN ANGLE TOWARD THE CENTER OF THE MAT. FOUR INCHES OF EACH STAKE SHALL INSTALL STAKES 1 TO INCHES FROM ALL EDGES REMAIN ABOVE THE SURFACE OF THE MAT. INCHES FROM MAT EDGE 6. MATS MAY BE INSTALLED IN UP TO 4 INCHES OF STANDING WATER. DRIVE STAKES AT ANGLE TOWARD CENTER OF MAT ENSURE CONSTANT CONTACT BETWEEN THE BOTTOM OF THE MAT OR PLANT ROOTS AND SOIL -BOISE. ID 2013-05-0

PRE-PLANTED COIR MAT INSTALLATION DETAIL

NOT TO SCALE

TEM Rel.

RECLAMATION



PLANT SCHEDULE

& DETAILS SHEET L-4

SHFFT 21 OF 21