
NASON CREEK - UPPER WHITE PINE REACH SUBREACH 2 STREAM HABITAT ENHANCEMENT CHELAN COUNTY, WASHINGTON 90% DESIGN - JUNE 7, 2016



SHEET LIST

- 1 COVER, SHEET LIST AND VICINITY MAP
- GENERAL NOTES LEGEND AND SUMMARY OF QUANTITIES
- 4 SITE PLAN OVERVIEW 5 EXISTING CONDITIONS, OWNERSHIP, AND SURVEY CONTROL
- 6 PROPERTY BOUNDARY SURVEY (LANDLINE)
- CONSTRUCTION SEQUENCING YEAR 1 NON IN-WATER WORK 8 - CONSTRUCTION SEQUENCING - YEAR 1 IN-WATER WORK 9 - CONSTRUCTION SEQUENCING - YEAR 2 IN-WATER WORK
- 10 CONSTRUCTION SEQUENCING YEAR 2 POST-IN WATER WORK
- 11 ACCESS, STAGING, DEWATERING AND EROSION CONTROL
- 12 ACCESS AND EROSION CONTROL DETAILS 13 ACCESS AND EROSION CONTROL DETAILS
- 14 ACCESS AND EROSION CONTROL DETAILS
- 15 PROPOSED CONDITIONS AND SHEET LAYOUT
- 16 PROPOSED MEANDER CHANNEL PLAN AND PROFILE 17 PROPOSED MEANDER CHANNEL UPSTREAM PLAN AND PROFILE
- 18 PROPOSED MEANDER CHANNEL DOWNSTREAM PLAN AND PROFILE
- 19 PROPOSED MEANDER CHANNEL GRADING CROSS SECTIONS
- 20 PROPOSED MEANDER CHANNEL GRADING CROSS SECTIONS 21 - PROPOSED MEANDER CHANNEL GRADING CROSS SECTIONS
- 22 DOWNSTREAM LEVEE REMOVAL GRADING PLAN AND PROFILE
- 23 PROPOSED CHANNEL FILL OVERVIEW AND PROFILE 24 PROPOSED CHANNEL FILL GRADING PLAN
- 25 PROPOSED CHANNEL FILL GRADING CROSS SECTIONS
- 26 PROPOSED CHANNEL FILL GRADING CROSS SECTIONS
- 27 PROPOSED CHANNEL FILL GRADING CROSS SECTIONS

- 28 PROPOSED BACKWATER ALCOVE PLAN AND PROFILE
- 29 PROPOSED BACKWATER ALCOVE GRADING CROSS SECTIONS
- 30 PROPOSED CULVERT RECONNECTION PLAN AND PROFILE
 31 PROPOSED CULVERT RECONNECTION GRADING CROSS SECTIONS
- 32 PROPOSED UPSTREAM MAINSTEM OBSTRUCTION PLAN AND PROFILE 33 - PROPOSED DOWNSTREAM MAINSTEM OBSTRUCTION PLAN AND PROFILE
- 34 PROPOSED LEVEE REMOVAL PLAN 35 PROPOSED LEVEE REMOVAL GRADING CROSS SECTIONS
- PROPOSED LEVEE REMOVAL GRADING CROSS SECTIONS 37 - PROPOSED LEVEE REMOVAL GRADING CROSS SECTIONS
- 38 PROPOSED LEVEE REMOVAL GRADING CROSS SECTIONS 39 PROPOSED LEVEE REMOVAL GRADING CROSS SECTIONS
- 40 TYPICAL SECTIONS RIFLLE AND LWS A-B
- 41 TYPICAL DETAILS FES LIFTS
- 42 TYPICAL DETAILS FES LIFTS 43 TYPICAL DETAILS FES LIFTS
- 44 TYPICAL DETAILS LWM
- 45 TYPICAL DETAILS LWM 46 TYPICAL DETAILS LWM
- 47 LWD CONSTRUCTION SEQUENCE
- 48 LWD CONSTRUCTION SEQUENCE
- 49 LWD CONSTRUCTION SEQUENCE 50 LWD CONSTRUCTION SEQUENCE 51 LWD CONSTRUCTION SEQUENCE
- 52 REVEGETATION PLAN (2017)
- 53 REVEGETATION PLAN (2018)
- 54 REVEGETATION DETAILS AND NOTES 55 REVEGETATION TABLES

COVER, SHEET LIST AND VICINITY MAP

RECLAMATION

1 SHEET 1 OF 55

HWY-97 WASHINGTON

ELLENSBURG

VICINITY MAP

NOT TO SCALE

LOCATION MAP

SEATTLE

THE CONTRACTOR SHALL ATTEND A PRE-CONSTRUCTION MEETING WITH OWNER AND OWNER'S REPRESENTATIVE PRIOR TO BEGINNING CONSTRUCTION.

ALL WORK SHALL CONFORM TO THE CURRENT EDITIONS OF STANDARD PLANS AND SPECIFICATIONS OF THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION (WSDOT), AND LOCAL STANDARDS UNLESS INDICATED OTHERWISE BY THE CONTRACT DOCUMENTS. IN CASE OF A CONFLICT BETWEEN THE REGULATORY STANDARDS OR SPECIFICATIONS, THE MORE STRINGENT WILL PREVAIL.

WDFW IN-WATER WORK PERIODS

IN-WATER WORK SHALL OCCUR DURING THE PERMITTED IN-WATER WORK PERIOD STATED IN THE HYDRAULIC PROJECT APPROVAL

EXISTING DATA

TOPOGRAPHIC DATA COLLECTED BY INTER-FLUVE USING RTK AND TOTAL STATION IN SEPTEMBER 2013; HYDROLOGY INFORMATION PROVIDED BY USBR AND WDOE; HYDRAULIC INFORMATION PROVIDED BY USBRY GIS DATA PROVIDED BY VARIOUS AGENCIES INCLUDING AERIAL PHOTOGRAPHY, LIDAR, FISH USE, SURFACE SOILS INFORMATION, LAND OWNERSHIP, AND TRANSPORTATION ROUTES. PROPERTY BOUNDARY SURVEY BY LANDLINE SURVEYORS, NOVEMBER 2013

SOILS

SEVEN SOILS TEST PITS WERE EXCAVATED ON AUGUST 26-27, 2014. SOILS PROFILES AVAILABLE UPON REQUEST

UTILITIES

THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR HAVING UTILITIES LOCATED PRIOR TO CONSTRUCTION ACTIVITIES.

THE CONTRACTOR SHALL CALL (800-424-5555) FOR UTILITY LOCATE PRIOR TO CONSTRUCTION

CALL 1-800-533-2891 TO ARRANGE FOR A BNSF UNDERGROUND CABLE LOCATE. BNSF FORM "UNDERGROUND CABLE LOCATION & ACKNOWLEDGE" WILL BE COMPLETED BY A BNSF REPRESENTATIVE AND COPY PROVIDED TO THE CONTRACTOR. THE CONTRACTOR MUST HAVE THIS COMPLETED FORM IN POSSESSION AT THE JOB SITE AT ALL TIMES.

THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE AFFECTED UTILITY SERVICE TO REPORT ANY DAMAGED OR DESTROYED UTILITIES.

THE CONTRACTOR SHALL PROVIDE EQUIPMENT OR LABOR TO AID THE AFFECTED UTILITY SERVICE IN REPAIRING DAMAGED OR DESTROYED UTILITIES AT NO

CONSTRUCTION STAKING

OWNER'S REPRESENTATIVE WILL PROVIDE STAKING OF PROJECT LIMITS. GRADE STAKES, AND ELEVATION CONTROL POINTS. SOME FIELD ADJUSTMENTS TO THE LINES AND GRADES ARE TO BE EXPECTED

CONTRACTOR SHALL MEET WITH THE OWNER AND OWNER'S REPRESENTATIVE TO DEFINE AND MARK LIMITS OF DISTURBANCE PRIOR TO MOBILIZATION OF

THE CONTRACTOR SHALL REPLACE DAMAGED OR DESTROYED CONSTRUCTION STAKES AT NO ADDITIONAL COST

CONSTRUCTION MATERIALS

ESTIMATED MATERIAL VOLUMES ARE APPROXIMATE IN-PLACE QUANTITY AND NOT FACTORED FOR EXPANSION OF EXCAVATED MATERIAL OR COMPACTION OF PLACED MATERIAL, MEASUREMENT AND PAYMENT SHALL NOT BE BASED ON WEIGHT TICKETS OR TRUCK MEASURE WITHOUT PRIOR WRITTEN APPROVAL

LOCATION, ALIGNMENT, AND ELEVATION OF LOGS AND LOGS WITH ROOT WADS ARE SUBJECT TO ADJUSTMENT BASED ON FIELD CONDITIONS, AND MATERIAL SIZE.

ANY EXCESS MATERIAL SHALL BE STOCKPILED NEATLY IN AN APPROVED LOCATION OF THE STOCKPILE AND STAGING AREA. AT COMPLETION OF WORK, THE MATERIAL SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.

TREE SALVAGE

ALL SAPLINGS AND TREES TO BE TRANSPLANTED OR REMOVED SHALL BE CLEARLY MARKED AND APPROVED BY THE OWNER AND OWNER'S REPRESENTATIVE

REMOVED VEGETATION SHALL BE INCORPORATED INTO LOG STRUCTURES AT NO ADDITIONAL COST, VEGETATION LARGER THAN 12" DIAMETER AND 15' LENGTH SHALL BE USED AS STRUCTURAL ELEMENTS, SMALLER MATERIAL SHALL BE USED AS

SELECT TREES REMOVED WITHIN CLEARING LIMITS SHALL BE REMOVED WHOLE WITH ROOT WAD AND USED IN RESTORATION CONSTRUCTION. TREES WILL BE FLAGGED FOLLOWING STAKING AND PRIOR TO CONSTRUCTION

LIVE TREES

ALL TREES NOT MARKED FOR REMOVAL SHALL BE LEFT STANDING UNDISTURBED. CONSTRUCTION ACTIVITY SHALL NOT DEBARK OR DAMAGE LIVE TREES. KEEP OUT OF DRIP LINE OF EXISTING TREES TO REMAIN

AQUATIC CONSERVATION MEASURES TO MEET NOAA ESA CONSULTATION REQUIREMENTS THROUGH ARBO II

- IN-WATER WORK PERIOD ALL WORK BELOW THE ORDINARY HIGH WATER (GENERALLY BELOW THE ELEVATION OF SHRUBBY VEGETATION GROWTH) MUST BE CONDUCTED DURING THE WDFW APPROVED IN-WATER WORK WINDOW JULY 1 AUGUST 15 (FINAL END DATE TO BE CONFIRMED IN CONSULTATION WITH WDFW).
- FISH PASSAGE FISH PASSAGE WILL BE PROVIDED FOR ANY ADULT OR JUVENILE FISH LIKELY TO BE PRESENT IN THE ACTION AREA DURING CONSTRUCTION AND STREAM ISOLATION AND DEWATERING IS REQUIRED DURING PROJECT IMPLEMENTATION.
- 15. POLLUTION AND EROSION CONTROL MEASURES IMPLEMENT THE FOLLOWING POLLUTION AND EROSION CONTROL MEASURES:
- PROJECT CONTACT: IDENTIFY A PROJECT CONTACT (NAME PHONE NUMBER AND ADDRESS) THAT WILL BE RESPONSIBLE FOR IMPLEMENTING POLLUTION AND EROSION CONTROL MEASURES.
- LIST AND DESCRIBE ANY HAZARDOUS MATERIAL THAT WOULD BE USED AT THE PROJECT SITE, INCLUDING PROCEDURES FOR INVENTORY, STORAGE, HANDLING, AND MONITORING; NOTIFICATION PROCEDURES; SPECIFIC CLEAN-UP AND DISPOSAL INSTRUCTIONS FOR DIFFERENT PRODUCTS AVAILABLE ON THE SITE: PROPOSED METHODS FOR DISPOSAL OF SPILLED MATERIAL: AND EMPLOYEE TRAINING FOR SPILL CONTAINMENT.
- TEMPORARILY STORE ANY WASTE LIQUIDS GENERATED AT THE STAGING AREAS UNDER COVER ON AN IMPERVIOUS SURFACE, SUCH AS TARPAULINS, UNTIL SUCH TIME THEY CAN BE PROPERLY TRANSPORTED TO AND TREATED AT AN APPROVED FACILITY FOR TREATMENT OF HAZARDOUS MATERIALS.
- d PROCEDURES BASED ON BEST MANAGEMENT PRACTICES TO CONFINE REMOVE AND DISPOSE OF CONSTRUCTION WASTE INCLUDING EVERY TYPE OF DEBRIS, DISCHARGE WATER, CONCRETE, CEMENT, GROUT, WASHOUT FACILITY, WELDING SLAG, PETROLEUM PRODUCT, OR OTHER HAZARDOUS MATERIALS GENERATED, USED, OR STORED ON-SITE.
- PROCEDURES TO CONTAIN AND CONTROL A SPILL OF ANY HAZARDOUS MATERIAL GENERATED, USED OR STORED ON-SITE, INCLUDING NOTIFICATION OF PROPER AUTHORITIES. ENSURE THAT MATERIALS FOR EMERGENCY EROSION AND HAZARDOUS MATERIALS CONTROL ARE ONSITE (E.G., SILT FENCE, STRAW BALES, OIL-ABSORBING FLOATING BOOM WHENEVER SURFACE WATER IS PRESENT).
- BEST MANAGEMENT PRACTICES TO CONFINE VEGETATION AND SOIL DISTURBANCE TO THE MINIMUM AREA, AND MINIMUM LENGTH OF TIME, AS NECESSARY TO COMPLETE THE ACTION, AND OTHERWISE PREVENT OR MINIMIZE EROSION ASSOCIATED WITH THE ACTION AREA
- NO UNCURED CONCRETE OR FORM MATERIALS WILL BE ALLOWED TO ENTER THE ACTIVE STREAM CHANNEL.
- STEPS TO CEASE WORK UNDER HIGH FLOWS, EXCEPT FOR EFFORTS TO AVOID OR MINIMIZE RESOURCE DAMAGE.

16. SITE PREPARATION

- FLAGGING SENSITIVE AREAS PRIOR TO CONSTRUCTION, VEGETATION TO REMAIN AND WETLANDS WILL BE FLAGGED TO MARK SENSITIVE AREAS THAT SHOULD NOT BE DISTURBED.
- STAGING AREA ESTABLISH STAGING AREAS FOR STORAGE OF VEHICLES EQUIPMENT, AND FUELS TO MINIMIZE EROSION INTO OR CONTAMINATION OF STREAMS AND FLOODPLAINS. PLACE STAGING AREA 150 FEET OR MORE FROM ANY NATURAL WATER BODY OR WETLAND IN AREAS WHERE TOPOGRAPHY DOES NOT RESTRICT SUCH A DISTANCE.
- TEMPORARY EROSION CONTROLS PLACE SEDIMENT BARRIERS PRIOR TO CONSTRUCTION AROUND SITES WHERE SIGNIFICANT LEVELS OF EROSION MAY ENTER THE STREAM DIRECTLY OR THROUGH ROAD DITCHES. TEMPORARY EROSION CONTROLS WILL BE IN PLACE BEFORE ANY SIGNIFICANT ALTERATION OF THE ACTION SITE AND WILL BE REMOVED ONCE THE SITE HAS BEEN STABILIZED FOLLOWING CONSTRUCTION ACTIVITIES
- STOCKPILE MATERIALS MINIMIZE CLEARING AND GRUBBING ACTIVITIES WHEN PREPARING STAGING, PROJECT, AND OR STOCKPILE AREAS, ANY LW. TOPSOIL AND NATIVE CHANNEL MATERIAL DISPLACED BY CONSTRUCTION WILL BE STOCKPILED FOR USE DURING SITE RESTORATION. MATERIALS USED FOR IMPLEMENTATION OF AQUATIC RESTORATION CATEGORIES (E.G., LW, BOULDERS, FENCING MATERIAL) MAY BE STAGED WITHIN THE 100-YEAR FLOODPLAIN

17. HEAVY EQUIPMENT USE

- **CHOICE OF EQUIPMENT SELECT HEAVY EQUIPMENT THAT MINIMIZES** ADVERSE EFFECTS TO THE ENVIRONMENT (E.G., MINIMALLY-SIZED, LOW PRESSURE TIRES, MINIMAL HARD TURN PATHS FOR TRACKED VEHICLES, TEMPORARY MATS OR PLATES WITHIN WET AREAS OR SENSITIVE SOILS).
- FUELING AND CLEANING AND INSPECTION FOR PETROLEUM PRODUCTS AND INVASIVE WEEDS
- ALL EQUIPMENT USED FOR INSTREAM WORK WILL BE CLEANED FOR PETROLEUM ACCUMULATIONS, DIRT, PLANT MATERIAL (TO PREVENT THE SPREAD OF NOXIOUS WEEDS), AND LEAKS REPAIRED PRIOR TO ENTERING THE PROJECT AREA. SUCH EQUIPMENT INCLUDES LARGE MACHINERY, STATIONARY POWER EQUIPMENT (E.G., GENERATORS, CANES), AND GAS-POWERED EQUIPMENT WITH TANKS LARGER THAN FIVE GALLONS.
- STORE AND FUEL FOUIPMENT IN STAGING AREAS AFTER DAILY USE INSPECT DAILY FOR FLUID LEAKS BEFORE LEAVING THE VEHICLE STAGING AREA FOR OPERATION

- THOROUGHLY CLEAN EQUIPMENT BEFORE OPERATION BELOW ORDINARY HIGH WATER OR WITHIN 50 FEET OF ANY NATURAL WATER BODY OR AREAS THAT DRAIN DIRECTLY TO STREAMS OR WETLANDS AND AS OFTEN AS NECESSARY DURING OPERATION TO REMAIN GREASE FREE.
- TEMPORARY ACCESS ROADS ALL ACCESS WILL BE FROM THE NORTH, NO ACCESS WILL BE ALLOWED FROM THE BNSF RIGHT-OF-WAY; NO PERSONNEL OR EQUIPMENT WILL BE PERMITTED TO CROSS THE BNSF TRACKS. EXISTING ACCESS ROADS WILL BE USED WHENEVER POSSIBLE, MINIMIZE THE NUMBER OF TEMPORARY ACCESS ROADS AND TRAVEL PATHS TO LESSEN SOIL DISTURBANCE AND COMPACTION AND IMPACTS TO VEGETATION. TEMPORARY ACCESS ROADS WILL NOT BE BUILT ON SLOPES WHERE GRADE, SOIL, OR OTHER FEATURES SUGGEST A LIKELIHOOD OF EXCESSIVE EROSION OR FAILURE. ALL TEMPORARY ACCESS ROADS WILL BE OBLITERATED OR REVEGETATED.
- d STREAM CROSSINGS THERE WILL ONLY BE ONE TEMPORARY CROSSING FOR EQUIPMENT TRAVEL OVER THE NEW CHANNEL. AFTER PROJECT COMPLETION, THE TEMPORARY STREAM CROSSING WILL BE ABANDONED AND THE STREAM CHANNEL AND BANKS RESTORED
- WORK FROM TOP OF BANK TO THE EXTENT FEASIBLE, HEAVY EQUIPMENT WILL WORK FROM THE TOP OF THE BANK, UNLESS WORK INSTREAM WOULD RESULT IN LESS DAMAGE TO THE AQUATIC ECOSYSTEM.
- TIMELY COMPLETION MINIMIZE TIME IN WHICH HEAVY EQUIPMENT IS IN STREAM CHANNELS, RIPARIAN AREAS, AND WETLANDS. COMPLETE EARTHWORK (INCLUDING DRILLING, EXCAVATION, DREDGING, FILLING AND COMPACTING) AS QUICKLY AS POSSIBLE. DURING EXCAVATION, STOCKPILE NATIVE STREAMBED MATERIALS ABOVE THE BANKFULL ELEVATION. WHERE IT CANNOT REENTER THE STREAM, FOR LATER USE.
- FOR WORK WITHIN THE LIMITS OF THE BNSF RIGHT-OF-WAY. THE CONTRACTOR WILL BE REQUIRED TO MEET ALL BNSF SAFETY AND INSURANCE REQUIREMENTS, AND WORK WITHIN 25 FEET OF THE TRACK CENTERLINE MAY ONLY BE ALLOWED WHEN A BNSF FLAGMAN IS PRESENT

18. SITE RESTORATION

- INITIATE REHABILITATION UPON PROJECT COMPLETION, REHABILITATE ALL DISTURBED AREAS IN A MANNER THAT RESULTS IN SIMILAR OR BETTER THAN PRE-WORK CONDITIONS THROUGH REMOVAL OF PROJECT RELATED WASTE, SPREADING OF STOCKPILED MATERIALS (SOIL, LW, TREES, ETC.) SEEDING, OR PLANTING WITH LOCAL NATIVE SEED MIXES OR PLANTS.
- SHORT-TERM STABILIZATION MEASURES MAY INCLUDE THE USE OF NON-NATIVE STERILE SEED MIX (WHEN NATIVE SEEDS ARE NOT AVAILABLE), WEED-FREE CERTIFIED STRAW, JUTE MATTING, AND OTHER SIMILAR TECHNIQUES SHORT-TERM STABILIZATION MEASURES WILL BE MAINTAINED UNTIL PERMANENT EROSION CONTROL MEASURES ARE EFFECTIVE, STABILIZATION MEASURES WILL BE IMPLEMENTED WITHIN THREE DAYS OF CONSTRUCTION COMPLETION.
- **REVEGETATION REPLANT EACH AREA REQUIRING REVEGETATION PRIOR TO** OR AT THE BEGINNING OF THE FIRST GROWING SEASON FOLLOWING CONSTRUCTION.
- **DECOMPACT SOILS DECOMPACT SOIL BY SCARIFYING THE SOIL SURFACE OF** ROADS AND PATHS, STREAM CROSSINGS, STAGING, AND STOCKPILE AREAS SO THAT SEEDS AND PLANTINGS CAN ROOT
- 401 CERTIFICATION TO MINIMIZE SHORT-TERM DEGRADATION TO WATER QUALITY DURING PROJECT IMPLEMENTATION, FOLLOW CURRENT 401 CERTIFICATION PROVISIONS OF THE FEDERAL CLEAN WATER ACT FOR MAINTENANCE OR WATER QUALITY STANDARDS DESCRIBED BY THE WASHINGTON DEPARTMENT OF ECOLOGY.
- 20. WORK AREA ISOLATION, SURFACE WATER WITHDRAWALS, AND FISH CAPTURE AND RELEASE - PRIOR TO EARTHWORK BELOW THE ORDINARY HIGH WATER, THE CONSTRUCTION AREA MUST BE ISOLATED AND FISH MUST BE REMOVED FROM THE WORK AREA. CONTRACTOR MUST COORDINATE THE TIMING OF IN-WATER WORK WITH THE CONSTRUCTION MANAGER TO ENSURE THAT WORK AREA ISOLATION AND DE-FISHING OCCUR IN THE CORRECT SEQUENCE.
- ISOLATE CAPTURE AREA CHELAN COUNTY STAFF WILL COORDINATE WORK AREA ISOLATION ACTIVITIES WITH ASSISTANCE FROM THE CONTRACTOR. IN GENERAL, WORK AREA ISOLATION WILL INCLUDE INSTALLATION OF BLOCK NETS AT UP AND DOWNSTREAM LOCATIONS OUTSIDE OF THE CONSTRUCTION ZONE TO EXCLUDE FISH FROM ENTERING THE PROJECT AREA NETS WILL REMAIN IN PLACE SECURED TO THE STREAM CHANNEL BED AND BANKS UNTIL CONSTRUCTION ACTIVITIES WITHIN THE STREAM CHANNEL ARE COMPLETE. IF BLOCK NETS OR TRAPS REMAIN IN PLACE MORE THAN ONE DAY, CHELAN COUNTY WILL MONITOR THE NETS AND OR TRAPS AT LEAST ON A DAILY BASIS TO ENSURE THEY ARE SECURED TO THE BANKS AND FREE OF ORGANIC ACCUMULATION AND TO MINIMIZE FISH PREDATION IN THE TRAP.
- CAPTURE AND RELEASE CHELAN COUNTY WILL COORDINATE THE FISH CAPTURE AND RELEASE ACTIVITIES WHICH WILL PROCEED GENERALLY AS FOLLOWS: FISH TRAPPED WITHIN THE ISOLATED WORK AREA WILL BE CAPTURED AND RELEASED USING METHODS TO MINIMIZE THE RISK OF INJURY. FISH WILL BE RELEASED AT A SAFE RELEASE SITE, PREFERABLY UPSTREAM OF THE ISOLATED REACH IN A POOL OR OTHER AREA THAT PROVIDES COVER AND FLOW REFUGE. FISH WILL BE COLLECTED IN THE BEST MANNER TO MINIMIZE POTENTIAL STRANDING AND STRESS BY SEINE OR DIP NETS AS THE AREA IS SLOWLY DEWATERED, BAITED MINNOW TRAPS PLACED OVERNIGHT, OR ELECTROFISHING (IF ELECTROFISHING WILL BE USED TO CAPTURE FISH FOR SALVAGE, NMFS'S ELECTROFISHING GUIDELINES WILL BE FOLLOWED (NMFS 2000).). FISH WILL BE HANDLED WITH EXTREME CARE AND KEPT IN WATER THE MAXIMUM EXTENT POSSIBLE DURING TRANSFER PROCEDURES. A HEALTHY ENVIRONMENT FOR THE STRESSED FISH SHALL BE PROVIDED--LARGE

BUCKETS (FIVE-GALLON MINIMUM TO PREVENT OVERCROWDING) AND MINIMAL HANDLING OF FISH. FISH WILL BE PLACED IN BUCKETS SEPARATE FROM SMALLER PREY-SIZED FISH. WATER TEMPERATURE IN BUCKETS WILL BE MONITORED TO ENSURE THE WELL-BEING OF CAPTURED FISH. IF BUCKETS ARE NOT BEING IMMEDIATELY TRANSPORTED, AERATORS WILL BE USED TO MAINTAIN WATER QUALITY. AS RAPIDLY AS POSSIBLE, BUT AFTER FISH HAVE RECOVERED, FISH WILL BE RELEASED. CAPTURE AND RELEASE WILL BE SUPERVISED BY A FISHERY BIOLOGIST. EXPERIENCED WITH WORK AREA ISOLATION AND SAFE HANDLING OF ALL FISH.

DEWATER CONSTRUCTION SITE - THE FIRST PHASE OF CONSTRUCTION OF THE NEW CHANNEL MEANDERS (YEAR 2 WORK) WILL BE CONSTRUCTED IN ISOLATION FROM THE EXISTING CHANNEL TO AVOID ANY IMPACTS TO FISH PASSAGE OR WATER QUALITY. ISOLATION BERMS WILL BE LEFT AT THE UPSTREAM AND DOWNSTREAM CONNECTION POINTS TO PREVENT SURFACE WATER ENTRY BETWEEN YEARS 1 AND 2. IN YEAR 1, DEWATERING WILL OCCUR AS NEEDED WITHIN THE CONSTRUCTION SITE TO FACILITATE EARTHWORK. IN YEAR 2, COFFERDAMS WILL BE USED IN THE MAIN CHANNEL TO DIVERT ALL OF THE NASON CREEK FLOW INTO THE NEW CHANNEL. THIS WILL OCCUR IN STAGES. THE FIRST STAGE INCLUDES GRADUALLY DIVERTING THE FLOW INTO THE NEW CHANNEL WITH FISH SCREENS IN PLACE AT THE UPSTREAM AND DOWNSTREAM ENDS TO PREVENT FISH FROM INITIALLY ENTERING THE NEW CHANNEL. THE INITIAL TURBID "RINSING" FLOWS WILL BE PUMPED FROM THE DOWNSTREAM END OF THE NEW CHANNEL UNTIL THE FLOWS CLEAR. THEN THE PUMP AND FISH SCREENS WILL BE REMOVED AND FISH PASSAGE WILL BE ALLOWED IN THE NEW CHANNEL. THE GRADUAL DIVERSION OF FLOWS WILL ALSO FACILITATE FISH RESCUE IN THE OLD CHANNEL AS THOSE FLOWS RECEDE CARE WILL BE TAKEN TO NOT DEWATER DOWNSTREAM AREAS. BEFORE FISH RESCUE OCCURS. IN YEAR 2. FOLLOWING FISH RESCUE AND ISOLATED BEHIND COFFERDAMS, DEWATERING WILL OCCUR AS NEEDED WITHIN THE CONSTRUCTION SITE TO FACILITATE EARTHWORK. DIVERSION BULK BAGS CAN BE FILLED WITH MATERIAL MINED FROM THE FLOODPLAIN AS LONG AS SUCH MATERIAL IS REPLACED AT END OF PROJECT. PUMP INTAKES USED IN AREAS WITH FISH MUST HAVE A FISH SCREEN(S) AND BE OPERATED IN ACCORDANCE WITH NMFS FISH SCREEN CRITERIA DESCRIBED BELOW IN SECTION II OF SURFACE WATER WITHDRAWALS. SEEPAGE WATER WILL BE PUMPED TO AN UPLAND AREA JUST UPSTREAM AND NORTH OF THE CONSTRUCTION AREA AND WILL BE ALLOWED TO FILTER THROUGH VEGETATION AND SOILS PRIOR TO RE-ENTERING THE STREAM CHANNEL. IF NECESSARY TO AVOID EROSION OR RE-ENTRY OF TURBID WATER INTO THE RIVER OR WETLANDS, WATER WILL BE PUMPED FIRST INTO A SETTLING BASIN DESCRIBED IN THESE PLANS.

SURFACE WATER WITHDRAWALS

- OTHER THAN THE DEWATERING PLAN DESCRIBED IN THESE PLANS, SURFACE WATER MAY NOT BE DIVERTED FROM NASON CREEK TO MEET CONSTRUCTION NEEDS
- FOR DEWATERING WORK, IF ESA-LISTED FISH MAY BE PRESENT, A FISH SCREEN MUST BE USED ON THE PUMP INTAKE TO AVOID JUVENILE FISH ENTRAINMENT THAT MEETS CRITERIA SPECIFIED BY NMFS. NMFS APPROVED FISH SCREENS HAVE THE FOLLOWING SPECIFICATIONS: (A) AN AUTOMATED CLEANING DEVICE WITH A MINIMUM EFFECTIVE SURFACE AREA OF 2.5 SQUARE FEET PER CFS, AND A NOMINAL MAXIMUM APPROACH VELOCITY OF 0.4 FEET PER SECOND (FPS), OR NO AUTOMATED CLEANING DEVICE, A MINIMUM EFFECTIVE SURFACE AREA OF 1 SQUARE FOOT PER CFS, AND A NOMINAL MAXIMUM APPROACH RATE OF 0.2 FPS; AND (B) A ROUND OR SQUARE SCREEN MESH THAT IS NO LARGER THAN 2.38 MM (0.094") IN THE NARROW DIMENSION, OR ANY OTHER SHAPE THAT IS NO LARGER THAN 1.75 MM (0.069") IN THE NARROW DIMENSION

RECLAMATION

GENERAL NOTES

6/7/16

2

SHEET 2 OF 55

SUMMARY OF ESTIMATED QUANTITIES Year 1 - Meander Channel Description Unit Excavation, including on-site material management CY 32,100 Excavation, riprap salvage for re-use CY 400 Imported gravel and cobble material CY 8,700 Backfill, channel bed material (select native & imported) 8,400 CY Backfill, for large wood structures (native & import) CY 6,900 Fabric Encapsulated Soil Lifts (FESL) LF 2,450 Rootwad log, 10"-15" DBH, 40' long EΑ 20 Rootwad log, 16"-21" DBH, 40' long EA 54 Rootwad log, 22"-28" DBH, 40' long 27 EA Log pole, 10"-15" dia, 40' long 44 EA Log pole, 16"-21" dia, 40' long 27 EA Log pole, 22"-28" dia, 40' long EA 6 Pile (vertical snag), 10"-15" dia, 30' long EΑ 12 Pile (vertical snag), 15"-18" dia, 30' long EA 129 Whole tree, 9"-15" DBH EΑ 9 Whole tree, 16"-21" DBH EΑ 23 Upland Area Woody Vegetation Plantings AC 0.37 Upland Area Herbaceous Vegetation Seed Mix AC 0.37 Mesic Area Woody Vegetation Plantings AC 3.10 Mesic Area Herbaceous Vegetation Seed Mix AC 3.10 Streambank Woody Vegetation Plantings AC 0.97 Year 2 - Levee Removal and Main Channel Fill Description Qty Unit Excavation, levee, including on-site material management 5,000 CY Excavation, riprap salvage for re-use 4,500 CY Backfill, channel fill with native material and salvaged riprap LF 29,300 Fabric Encapsulated Soil Lifts (FESL) 980 EA Rootwad log, 10"-15" DBH, 40' long EA 22 Rootwad log, 16"-21" DBH, 40' long EA 13 Rootwad log, 22"-28" DBH, 40' long 23 EΑ Log pole, 10"-15" dia, 40' long EΑ 2 Log pole, 16"-21" dia, 40' long

QUANTITIES ARE ESTIMATES, CONTRACTOR IS RESPONSIBLE FOR VERIFYING ITEMS AND QUANTITIES REQUIRED TO COMPLETE THE WORK AS SHOWN ON THE DRAWINGS AND REQUIRED IN THE SPECIFICATION.

Log pole, 22"-28" dia, 40' long

Whole tree, 9"-15" DBH

Whole tree, 16"-21" DBH

Pile (vertical snag), 12"-15" dia, 30' long

Pile (vertical snag), 15"-18" dia, 30' long

Upland Area Woody Vegetation Plantings

Mesic Area Woody Vegetation Plantings

Streambank Woody Vegetation Plantings

Upland Area Herbaceous Vegetation Seed Mix

Mesic Area Herbaceous Vegetation Seed Mix

ESTIMATED MATERIAL VOLUMES ARE APPROXIMATE IN-PLACE QUANTITY AND NOT FACTORED FOR EXPANSION OF EXCAVATED MATERIAL OR COMPACTION OF PLACED MATERIAL.

US SIEVE CLASS PERCENT PASSING

14" 12" 10" 84 -90 50 - 84 2-1/2" #4

5 - 15 3 - 10 #40

IMPORT MATERIAL - GRADATION A

US Sieve Class Percent Passing 93 - 100

2-1/2" 50 - 90 30 - 55 # 4 0 - 20

IMPORT MATERIAL - GRADATION B

SAFETY ALWAYS U.S. DEPAR GENERAL NOTES — LEGEND AND SUMMARY OF QUANTITIES

RECLAMATION

3

EΑ

EA

EA

EA

EA

EA

AC

AC

ACA

9

4

28

7

29

3.33


3.33


2.07


AC 2.07


AC 0.05


SHEET 3 OF 55






























SILT FENCE NOTES:


- THE SILT FENCE SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID USE OF JOINTS. WHEN JOINTS ARE NECESSARY, SILT FENCE SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6 INCH OVERLAP, AND BOTH ENDS SECURELY FASTENED TO THE POST. ALTERNATIVELY, OVERLAP AND INTERLOCK TWO POSTS WITH ATTACHED FABRIC AS REQUIRED TO MEET APPLICABLE REGULATIONS.
- THE SILT FENCE IS TO BE INSTALLED AT LOCATIONS SHOWN ON THE PLAN ALONG THE DOWNHILL PERIMETER OF CONSTRUCTION AREAS. THE FENCE POSTS SHALL BE SPACED A MAXIMUM OF 6 FEET APART AND DRIVEN SECURELY INTO THE GROUND A MINIMUM OF 24
- THE SILT FENCE SHALL HAVE A MINIMUM VERTICAL BURIAL OF 6 INCHES. ALL EXCAVATED MATERIAL FROM SILT FENCE INSTALLATION SHALL BE BACK-FILLED AND COMPACTED ALONG THE ENTIRE DISTURBED AREA.
- 4. STANDARD OR HEAVY DUTY SILT FENCE SHALL HAVE MANUFACTURED STITCHED LOOPS FOR 2 INCHES X 2 INCHES POST INSTALLATION.
- 5. SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY PROTECTED AND STABILIZED, OR AS DIRECTED BY CONTRACTING OFFICER.






ELEVATION

TURBIDITY CONTAINMENT FENCE NOT TO SCALE 14



TEMPORARY COFFERDAM SECTION




COFFERDAM SECTION IN WATER DEPTHS GREATER THAN 2.5'

BULK BAG COFFERDAM NOTES:

- BULK BAG COFFERDAM SHALL BE CONSTRUCTED OF SEVERAL UNITS OF BULK BAGS FILLED WITH STREAMBED COBBLES [WSDOT 9-03.11(2)] NO LARGER THAN SPECIFIED FOR INCORPORATION INTO THE PROJECT, AND ABUTTED SIDE BY SIDE TO CREATE A ROW THAT ISOLATES THE CONSTRUCTION SITE.
- IF WATER DEPTH EXCEEDS 85% OF THE BULK BAG HEIGHT. AN ADDITIONAL TOP ROW OF BULK BAGS SHALL BE INSTALLED. SUPPORTED BY TWO BOTTOM ROWS OF BULK BAGS. BULK BAG COFFERDAM SHALL BE SEALED BY COVERING THE COFFERDAM WITH PLASTIC SHEETING HELD IN PLACE BY STANDARD SANDBAGS
- THE PLASTIC SHEETING SHALL BE DRAPED ALONG THE CHANNEL BOTTOM ON BOTH SIDES OF THE COFFERDAM WITH OUTWARD EDGE OF SHEETING MINIMUM 4-FEET FROM TOE OF COFFERDAM. THE DRAPED PORTION OF PLASTIC SHEETING SHALL BE PINNED TO THE CHANNEL BED BY MINIMUM TWO ROWS OF
- 4. THE CONSTRUCTION SIDE EDGE OF PLASTIC SHEETING SHALL BE TOED INTO THE CHANNEL BED MINIMUM 1-FT. TOEING IN THE OUTWARD EDGE OF PLASTIC SHEETING SHALL OCCUR AFTER THE COFFERDAM IS CLOSED TO PREVENT TURBIDITY RELEASE TO THE WATERWAY
- 5. IF POSSIBLE, THE COFFERDAM SHALL BE EXTENDED ONTO A GRAVEL BAR AND OUT OF THE WATER. IF THE END MUST BE TERMINATED AT THE RIVERBANK, THE COFFERDAM SHALL BE TIGHTLY SEALED TO THE GROUND BY PLASTIC SHEETING AND STANDARD SANDBAGS. MULTIPLE LAYERS OF SHEETING AND SANDBAGS MAY BE REQUIRED TO FORM A WATERTIGHT SEAL.
- BULK BAGS SHALL BE CUBE-SHAPED POLYPROPYLENE WOVEN FABRIC BAGS WITH FULLY OPEN TOP, FLAT BOTTOM, FOUR LOOPS, MINIMUM 2-TON WEIGHT CAPACITY, MINIMUM 5:1 SAFETY FACTOR
- PLASTIC SHEETING SHALL BE MINIMUM 6-MIL THICKNESS. ROLL LENGTH SHALL COVER THE ENTIRE COFFERDAM WITHOUT SEAMS. MINIMUM 12-FT WIDE ROLL SHALL BE USED FOR SINGLE LAYER BULK BAG COFFERDAM. MINIMUM 16-FT WIDE ROLL SHALL BE USED FOR 2-LAYER STACKED BULK BAG COFFERDAM.
- 8. BULK BAG COFFERDAM SHALL BE COMPLETELY REMOVED AFTER CONSTRUCTION IS COMPLETED AND TURBIDITY HAS BEEN REMOVED. STONE IN BAGS AND ALL SYNTHETICS SHALL BE REMOVED FROM SITE AND LEGALLY DISPOSED OF BY CONTRACTOR.
- 9. MEASUREMENT AND PAYMENT FOR BULK BAG COFFERDAM, SAND BAGS, PLASTIC SHEETING, WASHED GRAVEL PLACEMENT, MAINTENANCE AND REMOVAL OF ALL MATERIALS SHALL BE INCIDENTAL TO THE LUMP SUM ALL INCLUSIVE COST FOR DIVERSION AND DEWATERING.
- 10. ALTERNATE COFFERDAM MATERIALS AND CONFIGURATIONS MAY BE ALLOWED BUT SHALL NOT BE IMPLEMENTED WITHOUT REVIEW AND APPROVAL BY THE OWNER'S REPRESENTATIVE. CONTRACTOR SHALL PROVIDE SHOP DRAWINGS AND/OR VENDOR CUT SHEETS FOR SUBSTITUTIONS.






SECTION


RECLAMATION ALWAY


ACCESS AND EROSION CONTROL DETAILS


6/7/16


14 SHEET 14 OF 55







































RECLAMATION BNSF ROW STA:0+76.5 EXISTING GROUND EXISTING LEVEE 2210 T 2210 2210 ELEV:2201.0 2210 STA:0+63.3 STA:0+10.5 ELEV:2199.0 PROPOSED MAINSTEM CHANNEL FILL -ELEV:2199.0 BNSF ROW __STA:0+54.9 __ELEV:2198.0 STA:0+36.8 STA:0+21.4_ STA:0+21.2 -PROPOSED NOTES ELEV:2192.0 ELEV:2198.0 ELEV:2198.0 2200 2200 2200 2200 BACKWATER <u></u>PROP. OHW 1. VIEW ORIENTATION IS LEFT TO RIGHT, LOOKING . ALCOVE BED DOWNSTREAM. STA:0+45.9 PLACED MAIN CHANNEL FILL WILL BE COMPRISED OF 2190 2190 2190 - 2190 SALVAGED ALLUVIAL SOILS FOR CONSTRUCTION OF FLOODPLAIN AND UPLAND TOPOGRAPHY. MATERIAL PROPOSED -STA:0+36.6 STA:0+42.5 BACKWATER WILL BE PLACED IN LIFTS WITH CONTROLLED MOISTURE ELEV:2192.9 EXISTING ELEV:2193.0 ALCOVE BED CONTENT AND COMPACTION, EXISTING RIPRAP MAINSTEM BED EMBANKMENT ALONG THE RAILROAD WILL REMAIN. 2180 ↓ 0+00 → 2180 0+80 0+80 0+80 PROPOSED BACKWATER CHANNEL - STA. 0+50 PROPOSED BACKWATER CHANNEL - STA. 1+30.34 BNSF ROW **BNSF ROW** -EXISTING LEVEE PROPOSED PROPOSED MAINSTEM 2210 - 2210 PROPOSED MAINSTEM CHANNEL FILL -BACKWATER 2210 CHANNEL FILL STA:0+57.9 STA:0+10.2 STA:0+73.6 ELEV:2201.0 ELEV:2199.0 ELEV:2199.0 STA:0+26.8 STA:0+21.3 STA:0+49.6 STA:0+63.3 ELEV:2198.0 FLFV:2198.0 ELEV:2199.2 2200 - 2200 2200 2200 SAFET MAINSTEM BED -2190 - 2190 2190 2190 STA:0+34.2 STA:0+44.0 STA:0+38.3 STA:0+41.9 ELEV:2192.0 ELEV:2192.0 ELEV:2195.0 - FXISTING 2184 | 0+00 PROPOSED BACKWATER ALCOVE BED -MAINSTEM BED 0+80²¹⁸⁰ 2180 0+00 PROPOSED BACKWATER CHANNEL - STA. 0+63.8 PROPOSED BACKWATER CHANNEL - STA. 1+50 ALWAYS **BNSF ROW BNSF ROW** 2210 PROPOSED MAINSTEM CHANNEL FILL 2210 EXISTING LEVEE EXISTING LEVEE PROPOSED MAINSTEM 2210 2210 STA:0+46.4 CHANNEL FILL STA:0+27.5 STA:0+21.9 ELEV:2195.6 ELEV:2198.0 STA:0+57.5 ELEV:2199.0 STA:0+77.7 FLFV:2199.0 ELEV:2201.0 2200 2200 PROP. OHW 2200 2200 STA:0+37.4 2190 2190 PROPOSED BACKWATER ALCOVE BED ELEV:2192.0 ELEV:2192.0 PROPOSED BACKWATER ALCOVE BED -EXISTING MAINSTEM BED — EXISTING MAINSTEM BED — → 2180 0+80 2180 | 0+00 2180 | 0+00 0+80 PROPOSED BACKWATER CHANNEL - STA. 0+82.4 PROPOSED BACKWATER CHANNEL - STA. 2+00 **BNSF ROW BNSF ROW** 2210 EXISTING LEVEE 2210 2210 PROPOSED MAINSTEM 2210 EXISTING LEVEE PROPOSED MAINSTEM STA:0+57.0 CHANNEL FILL STA:0+18.8 CHANNEL FILL -ELEV:2198.0 FLFV:2198.6 STA:0+64.2 STA:0+67.4 STA:0+33.0 STA:0+39.5 ELEV:2199.0 ELEV:2199.0 ELEV:2198.9 ELEV:2192.0 2200 2200 2200 2200 PROP. OHW STA:0+13.6 GRADE CONTROL (SEE PLAN) ELEV:2199.0 STA:0+26.1_ 2190 ELEV:2198.0 STA:0+37.0 - 2190 2190 - 2190 ELEV:2192.0 PROPOSED BACKWATER ALCOVE BED -STA:0+45.7 SCALE: 1" = 10' ELEV:2192.0 EXISTING MAINSTEM BED PROPOSED BACKWATER ALCOVE BED EXISTING MAINSTEM BED — 2180 0+00 0+80 0+80 PROPOSED BACKWATER CHANNEL - STA. 1+00 PROPOSED BACKWATER CHANNEL - STA. 2+50 **LEGEND** PROPOSED BACKWATER ALCOVE GRADING CROSS **EXISTING GRADE** SUBGRADE LIMIT SECTIONS PROPOSED GRADE PROPOSED OHW 29 SHEET 29 OF 55





BNSF ROW BNSF ROW PROPOSED BED -EXISTING MAINSTEM BED _STA:0+09.2 ELEV:2198.0 STA:0+27.8 ELEV:2189.9 2200 - PROPOSED BED STA:0+63.6 EXISTING MAINSTEM BED -ELEV:2194.0 ELEV:2194.0 ✓ PROP. OHW PROP. OHW 2190 - 2190 2190 2190 STA:0+36.1_ STA:0+46.6 STA:0+44.2 STA:0+33.0_ ELEV:2189.0 ELEV:2189.0 ELEV:2189.0 ELEV:2189.0 2180 | 0+00 0+80 0+80 0+80 0+80 PROPOSED CULVERT RECONNECTION - STA. 0+50 PROPOSED CULVERT RECONNECTION - STA. 2+00 BNSF ROW EXISTING MAINSTEM BED BNSF ROW STA:0+20.7 STA:0+07.7 ELEV:2198.0 EXISTING STA:0+68.5 MAINSTEM BED ELEV:2195.0 2200 2200 ELEV:2195.0 2200 STA:0+58.4 PROPOSED BED -∑ELEV:2194.0 PROPOSED BED -▽ PROP. OHW ⁷ ▽ PR<u>OP.</u> OHW 2190 - 2190 2190 2190 STA:0+44.6 STA:0+33.0 ELEV:2189.0 STA:0+31.8 ELEV:2189.0 ELEV:2189.0 0+80 0+80 2180 ↓ PROPOSED CULVERT RECONNECTION - STA. 2+17.40 PROPOSED CULVERT RECONNECTION - STA. 1+00 BNSF ROW STA:0+19.2 2200 - 2200 STA:0+62.0 ELEV:2194.0 ELEV:2195.0 PROPOSED BED -▽.P<u>RO</u>P. OHW 2190 2190 STA:0+31.9 __STA:0+42.1 ELEV:2189.0 **LEGEND** ELEV:2189.0 2180 0+00 0+80 2180 SUBGRADE LIMIT EXISTING GRADE PROPOSED CULVERT RECONNECTION - STA. 1+50 NOTE: VIEW ORIENTATION IS LEFT TO RIGHT, LOOKING DOWNSTREAM. SCALE: 1" = 10'


RECLAMATION ALWAYS THINK PROPOSED CULVERT RECONNECTION GRADING CROSS SECTIONS


31


SHEET 31 OF 55





























GENERAL INSTRUCTIONS FOR CONSTRUCTING FABRIC WRAPPED LIFTS

- UNROLL THE OUTER FABRIC (WOVEN COIR) PARALLEL TO THE LONG AXIS OF THE CHANNEL AND POSITION IT SO THAT 3 FEET EXTENDS FOR EMBEDMENT ON THE BANK SIDE OF THE FORMS (FIG B), AND A MINIMUM 3 FEET EXTENDS LENGTHWISE BEYOND THE LAST FORM FOR OVERLAP. DRAPE THE REMAINDER OF THE FABRIC OVER THE TOP OF THE FORMS ON THE STREAM SIDE (FIG B).
- 2. UNROLL THE INNER FABRIC (NON-WOVEN COIR) OVER THE TOP OF THE OUTER FABRIC AND POSITION IT SO THAT AT LEAST 1 FOOT OF THE INNER FABRIC EXTENDS AS AN EMBEDMENT LENGTH ON THE BANK SIDE OF THE FORMS (FIG C). DRAPE THE REMAINDER OF THE FABRIC OVER THE TOP OF THE FORMS ON THE STREAM SIDE AND ALIGN THE LONG EDGES OF THE INNER AND OUTER FABRICS. STRETCH AND PULL THE FABRIC LAYERS TO REMOVE WRINKLES.
- 3. PLACE GRADATION B / NATIVE FILL OVER THE FABRIC ON THE BANK SIDE OF THE FORMS TO A MAXIMUM COMPACTED DEPTH OF 12 INCHES. BACKFILL SHALL BE A MIX OF 50% IMPORTED GRADATION B AND 50% NATIVE MATERIAL. FINAL MIX SHALL HAVE 25-35% FINES. COMPACTED TO 86% STANDARD PROCTOR.
- 4. RIPARIAN SEED SHALL BE PLACED ON SOIL AND BENEATH FABRIC ON ALL EXPOSED SURFACES.
- 5. FOLD THE LOOSE ENDS OF THE TWO FABRIC LAYERS BACK OVER THE COMPACTED FILL MATERIAL AND STRETCH TIGHTLY TO REMOVE WRINKLES (FIG E). SECURE WITH MOODED STAYER
- PLACE 3" OF NATIVE FINES ON LIFT. PLACE LIVE CUTTINGS, AT 6" ON CENTER. ALTERNATE: LIVE CUTTINGS AS TUBLINGS WITH NO NATIVE FINES LAYER, 6" ON CENTER. REPEAT 2-6 TO FULL BANK HEIGHT.
- 8. ON THE TOP LIFT, EXCAVATE A KEY TRENCH 1' WIDE AND 0.75' DEEP ALONG THE EDGE OF THE OUTER FABRIC LAYER, PARALLEL TO THE FORMS. SECURE FABRIC IN
- BACKFILL & COMPACT THE KEY TRENCH WITH NATIVE FINES AND CONTINUE TO APPLY NATIVE FINES TO SMOOTHLY MERGE WITH EXISTING CONTOURS.


1 SUGGESTED CONSTRUCTION SEQUENCE FOR FABRIC WRAPPED LIFTS (END VIEW)
42 NOT TO SCALE





ALWAYS 6/7/16 TYPICAL DETAILS - FES LIFTS 42 SHFFT 42 OF 55

RECLAMATION

5











RECLAMATION VIBRATORY DRIVEN
 VERTICAL SNAG, TYP. LOG WITH ROOTWAD -FLOW ANGLED TIMBER VERTICAL SNAGS WHOLE TREE -PLAN VIEW PILE EMBEDMENT 15' MIN: MEASURE VERTICALLY NOT TO SCALE FROM POINT OF INSERTION VERTICAL SNAG, TYP. HORIZONTAL BREAK TOP END TO VARYING HEIGHTS AND CONDITIONS. LEAVE NO CUT WHOLE TREE ENDS. 15° MIN 45° MAX, OR AS OTHERWISE APPROVED BY THE CONTRACTING OFFICER TYPICAL DETAIL - ANGLED VERTICAL SNAG ANCHORING 1 TYPICAL D 46 NOT TO SCALE ALWAYS THINK LOG WITHOUT NOTES ROOTWAD -FLOODPLAIN ROUGHNESS WOOD SHALL BE COMPRISED OF 1 WHOLE TREE WITH A DBH OF 18" (-2"/+3") AND LENGTH OF 60' (-15'/+10'), 1 ROOTWAD LOG WITH A DBH OF 12" (-2"/+3") AND A LENGTH OF 40' (-5'/+5'), 2 VERTICAL SNAGS WITH A DBH OF 14" (-2"/+1") AND A LENGTH NO LESS THAN 30', AND SLASH AS APPROVED BY THE CONTRACTING OFFICER. THE WHOLE TREE MAY BE DECIDUOUS OR CONIFEROUS. SEE VIBRATORY DRIVEN TIMBER PILE, TYP -SPECIFICATIONS FOR ADDITIONAL MATERIAL REQUIREMENTS. SPECIFIC ORIENTATION OF LOGS AND VERTICAL SNAGS MAY VARY FROM TYPICAL DRAWINGS DEPENDING ON SIZE AND SHAPE OF MATERIAL DELIVERED OR SALVAGED. <u>SECTION VIEW</u> NOT TO SCALE BRACING TO EXISTING TREES OR INSTALLED VERTICAL LOGS WILL OCCUR AT LOCATIONS IDENTIFIED IN THE FIELD TO PROVIDE HORIZONTAL STABILITY. ACCEPTABLE VIBRATORY PILE DRIVING EQUIPMENT SHALL INCLUDE: HMC MOVAX SONIC SIDE GRIP VIBRATORY PILE DRIVER – MODEL SP80 OR EQUIVALENT. INSTALLATION BY EXCAVATION, HAMMERING OR VIBRATORY PLATE COMPACTOR 2 46 TYPICAL DETAIL - FLOODPLAIN ROUGHNESS SHALL NOT BE ALLOWED. NOT TO SCALE 6/7/16 TYPICAL DETAILS - LWM 46 SHEET 46 OF 55


SYSTEM CAD Rei. 20.1S (LMS TECH) FILENAME

















LIVE CUTTING DETAIL NOT TO SCALE

NOTES:


- 1. APPLY SEED MIX USING A SEED DRILLER OR IMPRINTER.
- 2. APPLY 1" WOOD CHIP MULCH TO ALL AREAS WITHOUT FABRIC.
- SEED AND MULCH SWALE ALONG ACCESS ROAD ALIGNMENT PER PLANS AS THE LAST STEP OF CONSTRUCTION.
- 4. PLANT RIPARIAN AND UPLAND AREAS PER SPECIES LISTS ON SHEET 55.
- 5. IRRIGATE ALL SEEDED AND PLANTED AREAS ONCE PER WEEK WITH 1" OF WATER FROM DATE OF PLANTING /SEEDING TO THE END OF OCTOBER.

BARE ROOT PLANT ROOT CROWN LEVEL WITH FINISH GRADE ROOT COLLAR SPREAD ROOTS EVENLY AROUND DIRT MOUND FIRMLY COMPACT SOIL UNDER ROOTS SO THAT FIRMLY HAND COMPACT ROOT COLLAR IS VISIBLE MOUND OF SOIL UNDER ABOVE SOIL **ROOTS FOR SUPPORT-**- NATIVE SOIL

BARE ROOT PLANTING NOTES:

- 1. PLANTING HOLE SHOULD BE DUG 2' WIDER THAN THE DIAMETER OF THE ROOT WAD.
- PLANT SHOULD BE PLACED SO THAT THE ROOT COLLAR IS VISIBLE ABOVE THE SOIL SURFACE. TO REACH THE DESIRED PLANTING HEIGHT MOUND FIRMLY COMPACTED SOIL IN THE BOTTOM OF THE PLANTING PIT
- BACKFILL THE HOLE UNTIL IT IS HALF FULL. LIGHTLY TAMP SOIL WITH YOUR FOOT TO REMOVE LARGE AIR POCKETS. WATER ROOTS UNTIL SOIL IS COMPLETELY SATURATED, WHILE GENTLY SHAKING THE PLANT'S TRUNK SO THAT ANY REMAINING AIR POCKETS ARE REMOVED.
- 4. FILL HOLE THE REMAINDER OF THE WAY. USE ANY REMAINING SOIL TO BUILD A TEMPORARY SOIL BERM ABOVE THE PERIMETER OF THE ROOTS. DEEP WATER THE PLANT AGAIN.

BARE ROOT DETAIL NOT TO SCALE



CONTAINER PLANTING NOTES:

- 1. DIG PLANTING HOLE 3" LARGER THAN ROOT BALL ON ALL SIDES, AND TO 3" DEEPER THAN THE HEIGHT OF THE ROOT BALL FROM BOTTOM OF CONTAINER TO ROOT COLLAR.
- 2. REMOVE CONTAINER AND MAKE THREE VERTICAL CUTS EQUALLY SPACED AROUND THE PERIMETER OF THE ROOT WAD TO A DEPTH OF 1/2 INCH.
- 3. PLANT SHOULD BE PLACED SO THAT THE ROOT COLLAR IS VISIBLE ABOVE THE SOIL SURFACE. TO REACH THE DESIRED PLANTING HEIGHT MOUND SOIL IN THE BOTTOM OF THE PLANTING HOLE AND FIRMLY COMPACT BY HAND UNTIL CORRECT HEIGHT IS REACHED.
- 4. BACKFILL AROUND ROOT BALL, FIRMLY COMPACTING SOIL BY HAND, TO A LEVEL 3/4" BELOW FINISH GRADE.

CONTAINER PLANT DETAIL NOT TO SCALE

SEED/GROUNDCOVER

GENERAL

ALL SEED SHALL COMPLY WITH REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS. WORK SHALL INCLUDE, BUT NOT BE LIMITED TO PURCHASE, STORAGE, INSTALLATION AND MAINTENANCE OF SEED THROUGHOUT THE PROJECT.

SEED TO BE APPLIED BY CONTRACTOR. IF GROUND DISTURBANCE OCCURS OUTSIDE THE DEPICTED OR STAKED LIMITS. CONTRACTOR SHALL SEED AREA WITH APPROPRIATE MIX AT NO COST TO OWNER.

SEEDING AREAS OVERLAP

QUALITY

SEED MIXES SHALL BE FREE OF NOXIOUS WEED SEEDS. SEEDS THAT HAVE BECOME WET. MOLDY, OR OTHERWISE DAMAGED, OR DO NOT MEET THE SPECIFICATIONS WILL BE REJECTED BY THE ENGINEER AT NO COST TO THE OWNER

LABELS

THE CONTENTS OF EACH BAG OF SEED DELIVERED SHALL BE CLEARLY LABELED AND THE FOLLOWING INFORMATION SHALL BE SUPPLIED UPON DELIVERY OF SEED:
A) COMMON NAME, GENUS, SPECIES, AND SUBSPECIES (WHEN APPLICABLE):

- B) AMOUNT OF PURE LIVE SEED (PLS) POUNDS OF EACH SPECIES IN EACH SEED MIX;
- C) PERCENT VIABILITY OF EACH SPECIES IN EACH SEED MIX;
- D) TOTAL DELIVERED WEIGHT, IN POUNDS, OF EACH SEED MIX:
- E) STATE AND COUNTY OF ORIGIN OF EACH SPECIES OF SEED USED IN MIXES; AND

F) NAME AND ADDRESS OF THE SEED SUPPLIER.

DELIVERY

THE DELIVERY DATE FOR SEED MIXES SHALL BE ARRANGED WITH THE CONTRACTOR, AND SUBJECT TO THE APPROVAL OF THE ENGINEER.

STORAGE

SEED SHALL BE STORED IN A COOL, DRY ENVIRONMENT UNTIL APPLICATION.

SOIL PREPARATION

RESTORE DISTURBED AREAS TO PRE-PROJECT GRADE.

PROPER SOIL PREPARATION PRIOR TO INSTALLATION OF SEED MIXES IS ESSENTIAL. ALL AREAS TO BE SEEDED SHALL HAVE A LOOSE, FRIABLE SEEDBED, FREE OF ANY WEED SEED, AND SHALL BE CONSTRUCTED TO MEET THE FINISH GRADE.

MULCHING AND CARE OF SEEDED AREAS

MULCH TO BE OBTAINED ON-SITE TO AVOID IMPORTING WEEDS.

APPLY 1" OF WOOD CHIP MULCH OVER ALL SEEDED AREAS. SEEDING AND MULCHING WILL TAKE PLACE AS THE LAST STEP OF CONSTRUCTION WHEN THE SITE IS DEMOBILIZED.

ANY AREAS SEEDED DURING CONSTRUCTION SHALL BE PROTECTED AND MAINTAINED THROUGHOUT THE CONSTRUCTION OF THE PROJECT AND UNTIL THE WORK IS ACCEPTED. NO CONSTRUCTION TRAFFIC WILL BE ALLOWED OVER A SEEDED OR PLANTED AREA ONCE THE SEED AND EROSION CONTROL MEASURES HAVE BEEN COMPLETED. FOOT TRAFFIC SHALL BE MINIMIZED ON SEEDED AREAS.

PLANTINGS

INDIVIDUAL PLANT LOCATIONS WILL BE DETERMINED IN THE FIELD BASED ON CONDITIONS. PLANTS SHALL BE OBTAINED FROM A LOCAL NURSERY WITHIN 150 MILES THAT SPECIALIZES IN THE PROPAGATION AND SALE OF NATIVE VEGETATION. ALL PLANTS SHALL BE WATERED UNTIL THE SOIL IS THOROUGHLY SATURATED IMMEDIATELY AFTER INSTALLATION. TO AVOID STEM ROT, MULCH MATERIAL SHALL BE PULLED BACK FROM THE PLANTS SO THAT MULCH DOES NOT CONTACT PLANT STEMS. ALL PLANTS SHALL BE SUBJECT TO INSPECTION BY THE OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION.

ليا ALWAY 6/7/16 REVEGETATION DETAILS AND NOTES 54 SHEET 54 OF 55

RECLAMATION

See	Seed Weight (lbs)				
Species	Common Name	% of Mix	2017	2018	Total
Elymus glaucus	Blue wild rye	33.3	15.6	18.8	34.4
Festuca idahoensis	Idaho fescue	33.3	15.6	18.8	34.4
Festuca ovina	Sheep's fescue	33.3	15.6	18.8	34.4
	•	Total Mix	46.8	56.3	103.1

314	
irrilino	
6/61, 20/	

Mesic Ar	ea Woody Vegetation P	lantings -20	17 1.88 acre	es, 2018 3.26 ac	res, Total 5.	14 acres	
Trees	<u> </u>			•	· ·		
Species	Common Name	% of Mix	Density	Form	2017 No.	2018 No.	Total No.
Pinus ponderosa	Ponderosa pine	5	10' OC	Tall 1 gal	41	72	113
Populus trichocarpa	Black cottonwood	10	10' OC	3" x 18" tube	82	143	225
	•	•		Sub-total	123	215	338
Shrubs							
Species	Common Name	% of Mix	Density	Form	2017 No.	2018 No.	Total No.
Amelanchier alnifolia	Pacific serviceberry	7.5	5' OC	Tall 1 gal	246	427	673
Crataegus douglassii	Black hawthorn	10	5' OC	3" x 18" tube	328	569	897
Holodiscus discolor	Ocean spray	5	5' OC	3" x 18" tube	164	285	449
Prunus emarginata	Oregon cherry	10	5' OC	Tall 1 gal	328	569	897
Rosa gymnocarpa	Dwarf rose	7.5	5' OC	Tall 1 gal	246	427	673
Rosa nutkana	Nootka rose	5	5' OC	Tall 1 gal	164	285	449
Salix lucida v. lasiandra	Pacific willow	5	5' OC	3" x 18" tube	164	285	449
Salix scouleriana	Scouler's willow	10	5' OC	3" x 18" tube	328	569	897
Spirea douglassi	Hardhack	15	5' OC	3" x 18" tube	492	853	1345
Symphoricarpos albus	Common snowberry	10	5' OC	3" x 18" tube	328	569	897
				Sub-total	2788	4838	7626
				Total	2911	5053	7964

Seeding Rate: 15 lbs/acre (77.5 lbs total)				Seed Weight (lbs)			
Species	Common Name	% of Mix	2017	2018	Total		
Carex obnupta	Slough sedge	17	4.7	8.2	12.9		
Carex stipata	Awlfruit sedge	17	4.7	8.2	12.9		
Deschampsia cespitosa	Tufted hairgrass	17	4.7	8.2	12.9		
Festuca idahoensis	Idaho fescue	17	4.7	8.2	12.9		
Glyceria grandis	American mannagrass	17	4.7	8.2	12.9		
Juncus effusus	Common rush	17	4.7	8.2	12.9		
	•	Total Mix	28.2	48.9	77.1		

subspicatum, Achillea millefolium, Epilobium angustifolium, Lupine sp., Solidago canadensis

Streambank Woody Vegetation Plantings - 2017 0.74 acres, 2018 0.28 acres, Total 1.02 acres								
Trees								
Species	Common Name	% of Mix	Density	Form	2017 No.	2018 No.	Total No.	Planting Notes
Populus trichocarpa	Black cottonwood	7.5	3' OC	3" x 18" tube	269	102	371	Middle of bank between OLW and OHW
		,		Sub-total	269	102	371	
Shrubs								
Species	Common Name	% of Mix	Density	Form	2017 No.	2018 No.	Total No.	Planting Notes
Cornus sericea sp.	Red-osier dogwood	10	3' OC	3" x 18" tube	359	136	495	Near and above OHW
Rosa nutkana	Nootka rose	10	3' OC	tall 1 gal	359	136	495	Near and above OHW
Salix exigua*	Coyote willow	10	3' OC	3" x 18" tube	359	136	495	Between OLW and OHW
Salix lucida lasiandra*	Pacific willow	10	3' OC	3" x 18" tube	359	136	495	High on bank above OHW
Salix sitchensis*	Sitka willow	10	3' OC	3" x 18" tube	359	136	495	On banks near OHW
Spirea douglassi	Hardhack	10	3' OC	3" x 18" tube	359	136	495	At and above OHW
Herbaceous sedge mats will co	mprise the remaining 32.5% of	the mix and w	ill include ""	Sub-total	2154	816	2970	
marked willows				Total	2423	918	3341	

Seeding Rate: 15 lb		Seed Weight (lbs)			
Species	Common name	% of mix	2017	2018	Total
Carex obnupta	Slough sedge	20	2.2	0.8	3.1
Eleocharis palustris	Spike rush	25	2.8	1.1	3.8
Elymus lanceolatus lanceolatus	Thickspike wheatgra	10	1.1	0.4	1.5
Festuca idahoensis	Idaho fescue	15	1.7	0.6	2.3
Juncus balticus	Baltic rush	20	2.2	0.8	3.1
Leymus cinereus	Basin wildrye	10	1.1	0.4	1.5
		Total Mix	11.1	4.2	15.3

						D
ALWAYS THINK SAFETY	U.S. DEPARMENT OF THE INTERIOR BUREAU OF RECLAMATION	COLUMBIA/SNAKE RIVER SALMON RECOVERY OFFICE FCRPS HABITAT IMPROVEMENT PROGRAM – WASHINGTON	NASON CREEK — UWP SUBREACH 2	STREAM HABITAT ENHANCEMENT	REVEGETATION TABLES	С
	501 Dorthust Avenue	Hood River, OR 97031 541.386.9003 www.interfluve.com				В
	4	inter-fluve	<u> </u>			
J.DM, ESIGNEI P EXAWN IM,GJ, HECKEL					04 /44 6/7/16	А
RE		55		BLI	ES	

RECLAMATION

SHEET 55 OF 55